


AR-010-527



Performance Tests of the Original  
Transonic Wind Tunnel Compressor  
and Circuit

Yoel Y. Link and Howard A. Quick


DSTO-TN-0150



1998009 077

] APPROVED FOR PUBLIC RELEASE

| [© Commonwealth of Australia



[~~DEIC QUALITY INSPECTED~~]

DEPARTMENT OF DEFENCE

DEFENCE SCIENCE AND TECHNOLOGY ORGANISATION

AQF98-12-2376

# Performance Tests of the Original Transonic Wind Tunnel Compressor and Circuit

*Yoel Y. Link and Howard A. Quick*

Air Operations Division  
Aeronautical and Maritime Research Laboratory

DSTO-TN-0150

## ABSTRACT

A detailed test programme of the AMRL Transonic Wind Tunnel was conducted. The objective of the test programme was to determine the pressure distributions around the tunnel circuit with larger nozzle exit areas. The existing high speed contraction, test section, model support mechanism, and downstream diffuser were removed for the tests. A variable nozzle and collector were designed and installed in place of the removed components to determine the effects of increasing the nozzle exit area. Three nozzle configurations were investigated, with a 38.3%, 44.4% and 58.1% increase in area relative to the existing test section area. Measurements were made of static pressure around the tunnel circuit, total pressure upstream and downstream from the compressor, and temperatures at various locations. Noise measurements were also made outside the tunnel complex and at four locations around the boundary of the site to determine the noise level of the wind tunnel.

## RELEASE LIMITATION

*Approved for public release*

DEPARTMENT OF DEFENCE

---

DEFENCE SCIENCE AND TECHNOLOGY ORGANISATION

*Published by*

*DSTO Aeronautical and Maritime Research Laboratory  
PO Box 4331  
Melbourne Victoria 3001 Australia*

*Telephone: (03) 9626 7000  
Fax: (03) 9626 7999  
© Commonwealth of Australia 1998  
AR-010-527  
May 1998*

**APPROVED FOR PUBLIC RELEASE**

# Performance Tests of the Original Transonic Wind Tunnel Compressor and Circuit

## Executive Summary

DSTO's transonic wind tunnel test capability, and its potential for improvement, has been the subject of considerable investigation over the last decade. These investigations have focused on meeting future wind tunnel test requirements for the Australian Defence Force. The outcome has been to select the Transonic Wind Tunnel located at AMRL Melbourne for a facility upgrade. Approval for this decision was given during 1994 and DSTO awarded a Design and Construct Contract in 1995.

The Transonic Wind Tunnel upgrade proposal defined a requirement to increase the Transonic Wind Tunnel test section area (cross section) by approximately 50% relative to the existing test section, and to operate at Mach numbers from 0.3 to 1.4, continuously variable. Increasing the test section size will allow larger models to be tested at a higher Reynolds number, which improves the accuracy of the test data acquired.

The upgrade proposal identified that an assessment of the potential to use existing wind-tunnel components from the current facility be conducted. The major components to be assessed included the compressor and heat exchanger, and a programme to test these components was specified.

The test programme covered a six month period, and was completed in June 1994. The objectives were to determine the tunnel circuit losses, maximum capacity of the heat exchanger, feasibility of retaining the existing compressor, and noise levels associated with operation of the present Transonic Wind Tunnel.

The high speed contraction, test section, model support mechanism, and downstream diffuser were removed for the tests. A variable nozzle and collector were designed and installed in place of the removed components to determine the effects of increasing the nozzle exit area. Three nozzle configurations were investigated, with an increase in the cross sectional area of the test section of 38.3%, 44.4% and 58.1% relative to the existing test section area. Measurements were made of static pressure around the tunnel circuit, total pressure upstream and downstream from the compressor, and temperatures at various locations including cooling water to the heat exchanger. Noise levels were also measured outside the tunnel near surrounding buildings and at the boundary of the site.

This report provides detailed performance data of the original Transonic Wind Tunnel which was acquired during this test programme. It is a comprehensive summary of the information provided to tenderers for use in compiling their submissions for potential upgrade options.

## Authors

### **Yoel Y. Link** Air Operations Division



*Yoel completed his Bachelor of Science in 1987 and his Bachelor of Engineering in Aeronautical Engineering in 1989, both at Sydney University, and joined the Aeronautical Research Laboratory at Melbourne the following year. He completed a Master of Business Administration in Technology Management in 1995 at Monash University. He has predominantly worked in Flight Mechanics and experimental aerodynamics in the Wind Tunnels. During this period he has accumulated experience in aerodynamics with the Jindivik, Tonic, PC-9, Mk82 store, Amphibious Transport (LPA) ship, and the Hydrographic Ship wind tunnel test programmes. He has also been responsible for the development of the wind tunnel data acquisition systems, and he has been involved with the Transonic Wind Tunnel Upgrade project.*

---

### **Howard A. Quick** Air Operations Division



*Howard completed a Bachelor of Engineering in Aeronautical Engineering at RMIT in 1988 and joined the Aeronautical Research Laboratory the following year. He has acquired experience in a number of areas including Computational Fluid Dynamics and aircraft performance while working in the Flight Mechanics Technology field, and has specialised in the area of experimental aerodynamics of RAAF aircraft and stores. In addition to this test programme in the transonic wind tunnel, two of the major wind tunnel test programmes that he has been involved with are the F/A-18 (IFOSTP), and the Mk-82 store.*

## Contents

<b>1. INTRODUCTION .....</b>	<b>1</b>
<b>2. EQUIPMENT DESCRIPTION .....</b>	<b>1</b>
<b>2.1 Nozzle .....</b>	<b>1</b>
<b>2.2 Collector.....</b>	<b>2</b>
<b>2.3 Heat Exchanger Temperature Probes and Support Frame.....</b>	<b>2</b>
<b>2.4 Temperature Probes .....</b>	<b>2</b>
<b>2.5 RPM Sensor.....</b>	<b>3</b>
<b>2.6 Psychrometer .....</b>	<b>3</b>
<b>2.7 Annubar and Digital Pressure Meter.....</b>	<b>3</b>
<b>2.8 Total Pressure Rakes and Total Pressure Probe .....</b>	<b>4</b>
<b>2.9 Tunnel Static Pressures .....</b>	<b>4</b>
<b>2.10 Pressure Measurement System .....</b>	<b>4</b>
<b>2.11 Blade Stagger Angle Setting Tool .....</b>	<b>4</b>
<b>2.12 Sound Level Measurement .....</b>	<b>5</b>
<b>3. TEST PROGRAMME PROCEDURE.....</b>	<b>5</b>
<b>3.1 Baseline Tests .....</b>	<b>6</b>
<b>3.2 Sound Level Tests.....</b>	<b>6</b>
<b>4. RESULTS.....</b>	<b>6</b>
<b>4.1 Tunnel Circuit Pressure.....</b>	<b>7</b>
<b>4.2 Tunnel Circuit Air Temperature.....</b>	<b>8</b>
<b>4.3 Cooling Water Temperature and Flow Rate .....</b>	<b>8</b>
<b>4.4 Measurement Accuracy.....</b>	<b>8</b>
<b>4.5 Sound Levels.....</b>	<b>9</b>
<b>5. CONCLUSION.....</b>	<b>9</b>
<b>6. ACKNOWLEDGEMENT .....</b>	<b>9</b>
<b>7. REFERENCES .....</b>	<b>9</b>
<b>APPENDIX A - TABULATED DATA.....</b>	<b>45</b>
<b>A.1 PRESSURE DATA - NOZZLE 1 - INCREMENTAL (N1 INCR) .....</b>	<b>45</b>
<b>A.2 PRESSURE DATA - NOZZLE 2 - INCREMENTAL (N2 INCR) .....</b>	<b>53</b>
<b>A.3 PRESSURE DATA - NOZZLE 3 - INCREMENTAL (N3 INCR) .....</b>	<b>61</b>
<b>A.4 PRESSURE COEFFICIENTS - NOZZLE COMPARISON (MAX1, MAX2).....</b>	<b>69</b>
<b>A.5 TEMPERATURE AND FLOW RATE DATA .....</b>	<b>71</b>
<b>A.6 SOUND LEVEL DATA .....</b>	<b>83</b>

## List of Figures

- Figure 1 – Schematic diagram of original transonic wind tunnel
- Figure 2 – Schematic diagram of transonic wind tunnel and equipment location
- Figure 3 – Nozzle exit looking upstream showing mounting of inserts, temperature probes, and total pressure probe
- Figure 4 – Nozzle and temperature probes looking downstream from inside the contraction towards the collector
- Figure 5 – Collector installed in plenum chamber looking upstream
- Figure 6 – Collector conical opening looking downstream
- Figure 7 – Location of temperature probes in front of heat exchanger
- Figure 8 – Heat exchanger temperature probes on support frame as installed
- Figure 9 – Air temperature probe
- Figure 10 – Surface mounted temperature probe in the plenum chamber
- Figure 11 – Thermowells in cooling water inlet and outlet pipes
- Figure 12 – Temperature and RPM indicator equipment
- Figure 13 – Inductive sensor shown opposite a compressor drive cardan shaft bolt
- Figure 14 – Differential pressure transducer and annubar
- Figure 15 – Compressor total pressure rakes
- Figure 16 – Total pressure rake #1 - Upstream of compressor
- Figure 17 – Total pressure rake #2 - Downstream of compressor
- Figure 18 – Static pressure hole fitting
- Figure 19 – Blade stagger angle setting tool
- Figure 20a – Stator blade leading edge protrusion
- Figure 20b – Stator blade leading edge protrusion
- Figure 21 – Sound level measurement locations
- Figure 22 – Pressure measurement for Nozzle 1 near the compressor and around the circuit for a range of compressor speeds
- Figure 23 – Pressure measurement for Nozzle 2 near the compressor and around the circuit for a range of compressor speeds
- Figure 24 – Pressure measurement for Nozzle 3 near the compressor and around the circuit for a range of compressor speeds
- Figure 25 – Nozzle Comparison - Pressure coefficients near the compressor for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)
- Figure 26 – Nozzle Comparison - Pressure coefficients around the circuit for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)
- Figure 27 – Nozzle 1 - Temperature variation for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)
- Figure 28 – Nozzle 2 - Temperature variation for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)
- Figure 29 – Nozzle 3 - Temperature variation for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)
- Figure 30 – Nozzle 1 - Temperature variation with compressor speed for the Incremental test

## Notation

AMRL	-	Aeronautical and Maritime Research Laboratory
Atm	-	atmosphere
H	-	Tunnel total pressure
INCR	-	Incremental tests
kPa	-	kilopascals
l/s	-	litres per second
M	-	Mach number
MAX1	-	Maximum compressor speed test during the day
MAX2	-	Maximum compressor speed test at night
m	-	metre
mm	-	millimetres
N1	-	Nozzle 1
N2	-	Nozzle 2
N3	-	Nozzle 3
P	-	Plenum chamber static pressure
psi	-	pounds per square inch
psia	-	pounds per square inch absolute
psid	-	pounds per square inch differential
RPM	-	revolutions per minute
<i>d</i>	-	inner diameter of the cooling water pipe
<i>h<sub>w</sub></i>	-	differential pressure measured in inches of water gauge
<i>q</i>	-	flow rate
<i>C<sub>p</sub></i>	-	pressure coefficient
<i>G<sub>f</sub></i>	-	flowing specific gravity of liquid
<i>K</i>	-	flow coefficient factor
<i>N<sub>vG</sub></i>	-	N factor for flowing volume with specific gravity determination

## 1. Introduction

Over the last decade attempts have been made to improve the transonic wind tunnel testing capability at the Aeronautical and Maritime Research Laboratory (AMRL). Initially, effort was directed at acquiring a new continuous flow tunnel with a 1.5 m square test section that would operate at Mach numbers from 0.3 to 1.6 and at pressures up to 3 atmosphere. Primarily due to Defence facilities budget constraints insufficient funds were available for this tunnel, so it was decided to upgrade the transonic wind tunnel (TWT) located at AMRL, Melbourne. The upgrade requirements are: to increase the test section area by at least 50% relative to the current test section area; to operate at Mach numbers of 0.3 to 1.4 continuously variable; and to operate at a pressure of 2 atmosphere (Reference 1).

The objectives of the tests described in this report were to determine:

- the tunnel circuit losses to provide a basis for increasing the maximum test section size that could be achieved using the existing compressor;
- the heat exchanger cooling water inlet and outlet temperatures and flow rate to assist with estimating the maximum capability of the existing heat exchanger;
- the feasibility of retaining the existing compressor by modifying the stator blade angles; and
- the noise levels emanating from the transonic wind tunnel when operating.

The tests required major modifications to the tunnel circuit inside the plenum and changing the angle of the stator blades in the compressor. The tunnel circuit, from the bolted joint in the contraction (Figure 1 – Station 2286) to the downstream end of the sliding diffuser (Figure 1 – Station 9828), was removed and replaced by a variable area nozzle and a collector. Measurements were taken of static pressure at various locations around the tunnel circuit, total pressure upstream and downstream of the compressor, and temperatures at various locations. The locations at which these measurements were made are shown in Figure 2. The preparation and testing was performed from December 1993 to June 1994.

## 2. Equipment Description

### 2.1 Nozzle

The nozzle consisted of a steel outer shell, with a range of timber inserts mounted on each surface to achieve the different nozzle exit areas. A schematic representation of the nozzle and collector in the plenum chamber is shown in Figure 2. The nozzle inserts were designed to continue the smooth surface curvature of the existing low-speed contraction (Figure 1 – Station 0 to Station 2286). This nozzle was designed and manufactured at AMRL.

The existing transonic wind tunnel test section dimensions are 810 mm x 532 mm, and the test section area is 0.43092 m<sup>2</sup>. In order to establish a reasonable definition of the compressor operating lines, three nozzle exit areas ranging from 0.6 m<sup>2</sup> to 0.7 m<sup>2</sup> were identified. Three nominal test section area increases (from the existing test section area) of 40%, 45% and 60% were decided upon. After design constraints, such as the

need to retain the contraction's smooth curvature without introducing any discontinuity, and to keep the design simple and inexpensive, three nozzle exit areas, as shown in Table 1, were designed and manufactured.

*Table 1. Nozzle Exit Areas*

Nozzle	Dimensions (mm)	Nozzle Area (m <sup>2</sup> )	Increase in area from original test section
N1	946 H x 631 W	0.5969	38.5%
N2	946 H x 657 W	0.6215	44.2%
N3	946 H x 720 W	0.6811	58.1%

Figures 3 and 4 show the four temperature probes and the total pressure probe mounted in the nozzle. The temperature probes were located 440 mm upstream of the nozzle exit, while the total pressure tube had its face aligned with the nozzle exit. The temperature probes were located 200 mm from the nozzle wall, while the total pressure tube had its face 110 mm below the upper insert's surface.

## 2.2 Collector

The collector, shown in Figure 2, was designed at AMRL and manufactured at Shearform Industries Pty Ltd. The collector was installed in place of the existing test section and diffuser and provided the interface between the rectangular exit of the nozzle and the round section of the existing diffuser at the sliding joint. The constant diameter tube and flared conical opening was used to avoid pulsations in the flow and to minimise losses in the air mass flow around the tunnel circuit.

Figure 2 gives the pertinent dimensions of the collector and nozzle as installed for the test programme. The collector has a constant internal diameter of 998 mm. The opening is flared at 30 degrees to form a conical end with a major diameter of 1350 mm. Figures 5 and 6 show the collector mounted in the plenum chamber prior to testing.

## 2.3 Heat Exchanger Temperature Probes and Support Frame

Four temperature probes were used to measure the temperature in front of the heat exchanger and these were mounted in a square shaped support frame (1 m x 1 m) with the probes fixed at the corners of the frame as shown in Figure 7. This support frame was mounted upstream of the heat exchanger on the central fairing using existing attachment points, as shown in Figure 8, with the lower two temperature probes located 1.5 m above the floor of the chamber. The temperature probes were located 350 mm upstream of the heat exchanger face.

## 2.4 Temperature Probes

Temperature measurements were taken at fourteen locations as shown in Figure 2 and consisted of:

1. freestream air temperature at four locations upstream of the heat exchanger and four locations at the bolted joint in the contraction (Figure 1 - Station 2286). These

- eight temperatures were measured using temperature probes, shown in Figure 9, containing ALPHA/THERM type M-KN 3045 platinum resistance temperature detectors;
2. the inner surface skin temperature of the plenum chamber measured at two locations at Station 5714 (Figure 2), using ALPHA/THERM type M-FK 220 thin film platinum resistance elements as shown in Figure 10;
  3. the outer surface skin temperature at two locations just downstream of the compressor using ALPHA/THERM type M-FK 220 thin film platinum resistance elements; and
  4. the temperature of the cooling water in the inlet and outlet heat exchanger pipes, using thermowells containing ALPHA/THERM type M-KN 3045 platinum resistance temperature detectors, as shown in Figure 11.

The temperatures were measured in series using the rotary selector and readout shown in figure 12.

## 2.5 RPM Sensor

The compressor rotational speed was measured using a Rechner IAS-10-A13-S inductive proximity sensor as shown in Figure 13, and a Kyodo Denki AP-05E digital tachometer. The sensor was located beside the compressor cardan shaft coupling and measured twelve bolt heads per revolution.

## 2.6 Psychrometer

The wet and dry bulb temperatures were measured using a psychrometer. The measurements were obtained outside the front entrance of the transonic wind tunnel building.

## 2.7 Annubar and Digital Pressure Meter

The water flow rate was measured using a Dieterich Standard, Diamond 2 Annubar Flow Sensor, in conjunction with a Moore Mycro XTC Differential Pressure Transducer to display pressure difference across the annubar shown in Figure 14. The pressures were recorded at each test condition and the flow rate calculated using a standard formula for this system.

The formula used to calculate the flow rate is given in Reference 2 and is:

$$q = N_{vG} K d^2 \sqrt{\frac{h_w}{G_f}}$$

where:

$q$  is the flow rate in units determined by the N factor;

$N_{vG}$  is the N factor for flowing volume with specific gravity determination, and is equal to 5.6665 for  $q$  in U.S. gallons per minute, and 0.3575 for  $q$  in litres per second (Reference 2, p. 9-37);

$K$  is the flow coefficient factor and is equal to 0.6337 for this annubar;

$d$  is the inner diameter of the pipe in inches and is equal to 6.065 in;

$h_w$  is the differential pressure measured in inches of water gauge<sup>1</sup>; and

$G_f$  is the flowing specific gravity of cooling water, and is approximately equal to 1.0 at the test conditions (Reference 2, p. E-10).

## 2.8 Total Pressure Rakes and Total Pressure Probe

Two total pressure rakes were used to measure pressures just upstream and downstream of the compressor as shown in Figure 15. Total pressure rake #1 (Figure 16) was installed approximately 280 mm upstream from the compressor's inlet guide vanes. Total pressure rake #2 (Figure 17) was installed approximately 180 mm behind the compressor's outlet guide vanes.

The total pressure rakes were manufactured from tubing with an outer diameter of 2.0 mm and internal diameter of 1.5 mm. The length from the stiffener to the tube face was 47 mm. Figures 16 and 17 give details of the radial positions of the tubes between the tunnel's outer shell and compressor's internal fairing.

## 2.9 Tunnel Static Pressures

Static pressure holes were located around the tunnel circuit at the positions shown in Figure 2. At each position a 2.5 mm hole was drilled through the tunnel shell and then an 11.1 mm diameter hole drilled to within 2 mm of the shell inner surface. The 11.1 mm hole was then tapped to fit a Swagelok SS-400-2-4ST elbow fitting as shown in Figure 18. All holes were deburred on the inner surface. Nylon pressure tubing (outer diameter 6.4 mm) was connected between the Swagelok fittings and a PSI pressure scanning system.

## 2.10 Pressure Measurement System

All pressures were measured and recorded using a PSI 8400 electronic pressure measurement and data acquisition system. Two pressure scanners with a range of  $\pm 5$  psid were used to measure the pressures. The static pressure in the tunnel plenum chamber was used as the reference pressure for the differential transducers, and it was measured using a 23 psia digiquartz pressure transducer.

The software controlling the data acquisition allows the user to specify the sampling parameters. The time between each data frame was set to 65000  $\mu$ s. The number of frames was set to 50, and the procedure was repeated 3 times with a 5 second delay between each sampling period. This resulted in 3 sets of pressure data for each data point. The tabulated pressure results are the mean of the 3 sets of data.

## 2.11 Blade Stagger Angle Setting Tool

The stagger angle of each of the compressor's stator blades was to be reduced by 10° using the tool shown in Figure 19. The following procedure was performed on the inlet guide vanes, and on the 1st, 2nd, and 3rd rows of stator vanes, to alter the blade stagger angle on each of the total of 176 vanes:

---

<sup>1</sup> The differential pressure transducer measurement units in the tests were kiloPascals, therefore, the reading must be converted, by dividing by 0.2491, to give a differential pressure in inches of water gauge.

1. each stator half ring was removed from the compressor casing and placed horizontally on a workbench;
2. using the horizontal surface of the half ring the tool was positioned so that the circular arc section of the tool was aligned with the circular stem of the blade;
3. three positions, indicating the current blade angle, current angle plus 10°, and current angle minus 10°, were scribed on the inner surface;
4. the two bolts holding the blade in position were loosened, the blade was rotated to the new angular setting (current minus 10°), and the two bolts tightened.

The change in the stator blade angle caused the leading edge of the blade to protrude beyond the edge of the inner ring (Figures 20a and 20b). Unfortunately, the protruding blades had the potential to interfere with the rotor blades and cause major damage to the compressor if it had been operated in this configuration.

After further consideration of the test requirements, it was decided that the baseline data would have to be sufficient and that there was little benefit in testing with a blade stagger angle reduction of less than 10°. Reduced angle settings (less than 10°) were considered but it was estimated that this would not provide the increased performance needed and consequently the tests with reduced blade stagger angles were not pursued.

## **2.12 Sound Level Measurement**

A Brüel and Kjær Type 2225 integrating sound level meter was used to measure the sound levels at locations within close proximity to the wind tunnel complex and at the perimeter of the site.

## **3. Test Programme Procedure**

The compressor tests were to be carried out in two phases. The first series of tests, the baseline tests, were carried out without making any modifications to the compressor, and the second series were to be carried out with the required modifications to the compressor stator blade stagger angles. Based on data requirements, three specific tests were identified for each of the three nozzles, one test acquiring data over a compressor speed range with 20 RPM increments, a maximum compressor speed test during normal tunnel running hours, and a maximum compressor speed test at night. In both maximum speed tests data was acquired at 5 minute intervals for up to a maximum of 3 hours. The test programme carried out is contained in Table 2. All the tests were made at a tunnel starting pressure of approximately 0.5 Atm.

*Table 2. Transonic wind tunnel compressor test programme*

Test Case	20 RPM increments (INCR)		Max RPM (MAX1)		Max RPM at night (MAX2)	
	Nozzle Area Increase	Baseline	Blade mods.	Baseline	Blade mods.	Baseline
38.5% (N1)	9/5/94 AM	n/a	10/5/94 AM	n/a	10/5/94 PM	n/a
44.2% (N2)	11/5/94 PM	n/a	12/5/94 AM	n/a	12/5/94 PM	n/a
58.1% (N3)	13/5/94 PM	n/a	17/5/94 AM	n/a	16/5/94 PM	n/a

### 3.1 Baseline Tests

For the 20 RPM incremental tests (INCR) the compressor was operated from 400 to 1160 RPM (maximum operating RPM = 1200). Operation at 1160 RPM was limited to less than 2 minutes to avoid thermal overload of the electric motor control unit.

For the maximum continuous RPM tests (MAX1 and MAX2), which were carried out over 3 hours, the compressor speed was limited to 1100 RPM. However, the maximum continuous RPM tests for Nozzle 3 (58.1% increase in test section area) could only be carried out over a period of 2.5 hours due to overheating in the electric motor control unit.

### 3.2 Sound Level Tests

Sound level measurements were acquired within close proximity to the wind tunnel complex and around the AMRL site at four locations as shown in Figure 21. Measurements were only recorded during the tests on Nozzle 1, as it was shown by a limited sample of measurements that the sound levels did not vary considerably with the different nozzle areas.

## 4. Results

Appendix A contains the tabulated results for the baseline tests. The temperature data for all the tests is included and the nomenclature used is given in Table 3. The complete pressure data for the incremental tests is also included, and pressure coefficients over each entire run are calculated for the maximum continuous RPM test cases. The format of the pressure data is given in Table 4. The mean pressure data in Appendix A is presented as both differential and absolute pressure values. The pressure data is presented graphically in Figures 22-26, and the temperature data is presented in Figures 27-30.

Analysis of the pressure data presented in Figures 22-26 should take into consideration the characteristics of this wind tunnel, particularly that there is no controller to hold the tunnel pressure constant over the test duration. This is evident by the increase in static pressure of approximately 1 psi (at 0 RPM) from the start of the test to the end of the test.

*Table 3. Description of temperature data format*

Notation	Description
Time	Time of data acquisition
RPM	Compressor speed
H (kPa)	Tunnel total pressure, in kilopascals, which is taken to be the static pressure in the settling chamber
P (kPa)	Plenum chamber static pressure in kilopascals, measured by 23 psia digiquartz
M	Mach number calculated from P and H
T1 - T4	Temperatures ( $^{\circ}$ C) in nozzle
T5 - T8	Temperatures ( $^{\circ}$ C) in front of heat exchanger
T9 - T10	Temperatures ( $^{\circ}$ C) on inner surface of plenum chamber skin at Station 5714 (Figure 1)
T11 - T12	Temperatures ( $^{\circ}$ C) on the tunnel outer skin 1125 mm downstream from compressor
T13	Temperature ( $^{\circ}$ C) of heat exchanger outlet cooling water
T14	Temperature ( $^{\circ}$ C) of heat exchanger inlet cooling water
Twet ( $^{\circ}$ F)	Wet bulb temperature in degrees Fahrenheit
Tdry ( $^{\circ}$ F)	Dry bulb temperature in degrees Fahrenheit
$q$ (l/s)	Heat exchanger cooling water inlet flow rate in litres per second

*Table 4. Description of pressure data format*

Transducer	sc-01 (Scanner 1)	sc-02 (Scanner 2)
1	Static pressure in plenum chamber	Static pressure in plenum chamber
2	Reference check pressure	Reference check pressure
3	Compressor Rake 1 Tube 1 (R1T1)	Static pressure before first corner (B1)
4	Compressor Rake 1 Tube 2 (R1T2)	Static pressure after first corner (A1)
5	Compressor Rake 1 Tube 3 (R1T3)	Static pressure before second corner (B2)
6	Compressor Rake 1 Tube 4 (R1T4)	Static pressure before third corner (B3)
7	Compressor Rake 1 Tube 5 (R1T5)	Static pressure after third corner (A3)
8	Compressor Rake 2 Tube 1 (R2T1)	Static pressure after fourth corner (A4)
9	Compressor Rake 2 Tube 2 (R2T2)	Static pressure in settling chamber (SC)
10	Compressor Rake 2 Tube 3 (R2T3)	Static pressure in plenum chamber (PC)
11	Compressor Rake 2 Tube 4 (R2T4)	Total pressure at nozzle exit (TOT)
12	Compressor Rake 2 Tube 5 (R2T5)	

#### 4.1 Tunnel Circuit Pressure

The effect of the different nozzle exit areas on the pressures around the tunnel circuit is presented using pressure coefficients. The pressure coefficients were calculated using the following formula:

$$C_p = \frac{P(\text{location}) - P(\text{ref})}{q(\text{ref})}$$

where:

$P(\text{location})$  = pressure reading at tunnel circuit location

$P(\text{ref})$  = static pressure in plenum chamber

$q(\text{ref})$  = dynamic pressure in the nozzle

The pressure coefficients were calculated for each tunnel circuit location and are plotted in Figures 25 and 26. The pressure coefficients presented are averaged "mean" values. The standard deviations associated with these averages indicate little variation across the data points sampled.

## 4.2 Tunnel Circuit Air Temperature

The temperature plots given in Figures 27-30, are an average of the data taken at each of the locations, for example, the temperature in front of the heat exchanger is calculated from an average of T1, T2, T3 and T4. Obviously, at those locations where only one measuring device was located, in the inlet and outlet cooling water pipes, the data cannot be averaged. The data is plotted for all the maximum continuous RPM tests as the objective of acquiring the temperature data was to determine the temperature variation with time at the maximum compressor speed. A plot of the variation of temperature with RPM (an incremental test) is given for Nozzle 1 in Figure 30. Similar trends occurred for the other nozzles but they are not shown graphically.

At the completion of the Nozzle 2 - Incremental tests the temperature data was analysed and one of the heat exchanger temperature probes (T1) was found to be in error over the RPM range 0-680. Therefore, in analysing the data from Appendix A.5, T1 was not used in calculating the mean temperature in front of the heat exchanger over the RPM range 0 - 680.

## 4.3 Cooling Water Temperature and Flow Rate

During two of the maximum RPM tests a malfunction of the cooling tower water shut off valve occurred causing partial closure of the valve. This was immediately recognised by the decrease in the water flow rate from 58.0 l/s to 40.9 l/s in the case of Nozzle 2 - MAX1, and from 58.3 l/s to 41.5 l/s in the case of Nozzle 3 - MAX1. This occurrence is clearly shown by the sharp increase (approximately 1°C - 1.5°C) in the temperatures at the heat exchanger, nozzle and cooling water outlet in the corresponding graphs in Figures 28 and 29 at the elapsed times of 2 hours 45 minutes and 1 hour 30 minutes respectively. The valve was manually returned to the fully open position and the flow rate returned to its regular level.

The water flow rate was measured using a differential pressure transducer in conjunction with an annubar as described in section 2.7. The readout of the differential pressure transducer during the tests varied between 11.0 kPa and 13.0 kPa, corresponding to 55.3 l/s and 60.0 l/s respectively. The flow rate value in the tabulated data is an average of the high and low values observed at each test point.

## 4.4 Measurement Accuracy

The PSI 8400 pressure measurement system has an accuracy of 0.5% of the full-scale value of the transducers. In this test  $\pm 5$  psid transducers were used and the error in the pressure data is therefore  $\pm 0.025$  psi.

The temperature equipment was calibrated over the range of temperatures required and found to be accurate to within  $\pm 0.6^{\circ}\text{C}$ .

#### 4.5 Sound Levels

The results of the sound level measurements are contained in Appendix A.6.

### 5. Conclusion

This report describes the transonic wind tunnel tests performed in support of the AMRL transonic wind tunnel upgrade project. A full description of the equipment used, the location of all equipment, and a compilation of all the test results is presented.

The data acquired from these tests will be used, by the tenderers for the Transonic Wind Tunnel Upgrade project, in determining the different option packages put forward that will provide a range of increases in the wind-tunnel performance.

### 6. Acknowledgement

The authors would like to thank I. Amott, D. Carnell, J. Clayton, A. Gonzalez, S. Lam, P. Malone, and N. Matheson for their assistance in the preparation and testing of the transonic wind tunnel.

### 7. References

1. Link, Y., Pollock, N., Matheson, N., *Upgrading the Transonic Wind Tunnel at the Aeronautical and Maritime Research Laboratory*, Proceedings of the Sixth Australian Aeronautical Conference, Melbourne Australia, 1995.
2. Miller, R.W., *Flow Measurement Engineering Handbook*, McGraw-Hill Publishing Company, 1989.
3. Sverdrup Technology Inc., *Final Report from Consultancy Services for Transonic Wind Tunnel Redevelopment under the direction of Aeronautical Research Laboratory*, January 28 1994.
4. Pope, A., Goin, K.L., *High-Speed Wind Tunnel Testing*, John Wiley & Sons, 1965.
5. Rae, W.H., Pope, A., *Low-Speed Wind Tunnel Testing*, John Wiley & Sons, 1984.
6. Willis, J.B., *The A.R.L. Transonic Wind Tunnel*, ARL Aero Note 412, September 1982.






FIGURE 1. SCHEMATIC DIAGRAM OF





FIGURE 1. SCHEMATIC DIAGRAM OF ORIGINAL TRANSONIC WIND TUNNEL



OF ORIGINAL TRANSONIC WIND TUNNEL

3




FIGURE 2. SCHEMATIC DIAGRAM OF TRANSC







FIGURE 2. SCHEMATIC DIAGRAM OF TRANSONIC WIND TUNNEL AND EQUIPMENT LOCATION




RANSONIC WIND TUNNEL AND EQUIPMENT LOCATION




*Figure 3. Nozzle exit looking upstream showing mounting of inserts, temperature probes, and total pressure probe*




*Figure 4. Nozzle and temperature probes looking downstream from inside the contraction towards the collector*



*Figure 5. Collector installed in plenum chamber looking upstream*




*Figure 6. Collector conical opening looking downstream*



Tips of Probes are located 350 mm forward of heat exchanger face. (see figure 2)

Figure 7. Location of temperature probes in front of heat exchanger




*Figure 8. Heat exchanger temperature probes on support frame as installed*



*Figure 9. Air temperature probe*



*Figure 10. Surface mounted temperature probe in the plenum chamber*



*Figure 11. Thermowells in cooling water inlet and outlet pipes*





Figure 12. Temperature and RPM indicator equipment



*Figure 13. Inductive sensor shown opposite a compressor drive cardan shaft bolt*




Figure 14. Differential pressure transducer and annubar




Figure 15. Compressor total pressure rakes




Figure 16. Total pressure rake #1 – Upstream of compressor







Figure 17. Total pressure rake #2 – Downstream of compressor




*Figure 18. Static pressure hole fitting*



*Figure 19. Blade stagger angle setting tool*



*Figure 20a. Stator blade leading edge protrusion*



*Figure 20b. Stator blade leading edge protrusion*




Figure 21. Sound level measurement locations

- 1 - Main Gate (North)
- 2 - Car Park (East)
- 3 - Building 27 (South)
- 4 - Car Park (West)




Figure 22. Pressure measurement for Nozzle 1 near the compressor and around the tunnel circuit for a range of compressor speeds




Figure 23. Pressure measurement for Nozzle 2 near the compressor and around the tunnel circuit for a range of compressor speeds




Figure 24. Pressure measurement for Nozzle 3 near the compressor and around the tunnel circuit for a range of compressor speeds





Figure 25. Nozzle comparison - Pressure coefficients near the compressor for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)





Figure 26. Nozzle comparison - Pressure coefficients around the circuit for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)




Figure 27. Nozzle 1 - Temperature variation for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)




Figure 28. Nozzle 2 - Temperature variation for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)




Figure 29. Nozzle 3 - Temperature variation for the maximum compressor speed tests during the day (MAX1) and the night (MAX2)




Figure 30. Nozzle 1 - Temperature variation with compressor speed for the Incremental test

DSTO-TN-0150

## **APPENDIX A - Tabulated Data**

### **A.1 Pressure Data - Nozzle 1 - Incremental (N1 INCR)**

DSTO-TN-0150

RPM=400	H=50.38	P=49.15	P (psi) = 7.128				RPM=420	H=51.03	P=49.66	P (psi) = 7.202				
Mon	May		9	15:08:21	1994		Mon	May		9	15:22:14	1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	-0.001	7.128	7.128	1	0.000	-0.001	7.202	7.202	1	0.000	-0.001	7.202	7.202
2	0.030	0.030	7.159	7.159	2	0.030	0.030	7.232	7.232	2	0.030	0.030	7.232	7.232
3	0.128	0.080	7.257	7.208	3	0.140	0.087	7.342	7.289	3	0.140	0.087	7.342	7.289
4	0.125	0.070	7.253	7.198	4	0.136	0.076	7.339	7.278	4	0.136	0.076	7.339	7.278
5	0.123	0.094	7.251	7.222	5	0.134	0.102	7.336	7.304	5	0.134	0.102	7.336	7.304
6	0.122	0.197	7.251	7.325	6	0.133	0.214	7.335	7.416	6	0.133	0.214	7.335	7.416
7	0.119	0.198	7.248	7.326	7	0.130	0.214	7.332	7.417	7	0.130	0.214	7.332	7.417
8	0.257	0.197	7.385	7.325	8	0.280	0.214	7.482	7.416	8	0.280	0.214	7.482	7.416
9	0.252	0.180	7.380	7.308	9	0.274	0.196	7.477	7.398	9	0.274	0.196	7.477	7.398
10	0.235	-0.001	7.363	7.128	10	0.255	-0.001	7.457	7.202	10	0.255	-0.001	7.457	7.202
11	0.216	0.180	7.345	7.309	11	0.235	0.196	7.437	7.399	11	0.235	0.196	7.437	7.399
12	0.181		7.309		12	0.195		7.398		12	0.195		7.398	
RPM=440	H=51.23	P=49.69	P (psi) = 7.207				RPM=460	H=51.40	P=49.73	P (psi) = 7.212				
Mon	May		9	15:25:55	1994		Mon	May		9	15:29:04	1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	-0.001	7.206	7.206	1	0.000	-0.001	7.212	7.212	1	0.000	-0.001	7.212	7.212
2	0.030	0.030	7.237	7.236	2	0.030	0.030	7.243	7.242	2	0.030	0.030	7.243	7.242
3	0.159	0.098	7.366	7.305	3	0.175	0.107	7.387	7.320	3	0.175	0.107	7.387	7.320
4	0.154	0.086	7.361	7.293	4	0.170	0.095	7.382	7.307	4	0.170	0.095	7.382	7.307
5	0.152	0.116	7.359	7.322	5	0.167	0.127	7.379	7.340	5	0.167	0.127	7.379	7.340
6	0.150	0.241	7.357	7.447	6	0.166	0.264	7.378	7.476	6	0.166	0.264	7.378	7.476
7	0.147	0.242	7.354	7.448	7	0.162	0.264	7.374	7.477	7	0.162	0.264	7.374	7.477
8	0.317	0.242	7.524	7.448	8	0.349	0.264	7.562	7.477	8	0.349	0.264	7.562	7.477
9	0.310	0.222	7.517	7.429	9	0.340	0.243	7.553	7.456	9	0.340	0.243	7.553	7.456
10	0.288	0.000	7.494	7.206	10	0.315	-0.001	7.528	7.212	10	0.315	-0.001	7.528	7.212
11	0.266	0.222	7.472	7.429	11	0.291	0.243	7.503	7.456	11	0.291	0.243	7.503	7.456
12	0.220		7.427		12	0.239		7.452		12	0.239		7.452	
RPM=480	H=51.54	P=49.71	P (psi) = 7.210				RPM=500	H=51.69	P=49.69	P (psi) = 7.207				
Mon	May		9	15:31:03	1994		Mon	May		9	15:33:14	1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	-0.001	7.210	7.209	1	0.000	0.000	7.207	7.206	1	0.000	0.000	7.207	7.206
2	0.030	0.030	7.240	7.240	2	0.030	0.030	7.237	7.237	2	0.030	0.030	7.237	7.237
3	0.191	0.118	7.401	7.327	3	0.207	0.128	7.414	7.335	3	0.207	0.128	7.414	7.335
4	0.186	0.104	7.395	7.314	4	0.202	0.113	7.408	7.319	4	0.202	0.113	7.408	7.319
5	0.182	0.140	7.392	7.349	5	0.198	0.152	7.405	7.358	5	0.198	0.152	7.405	7.358
6	0.180	0.289	7.390	7.499	6	0.195	0.313	7.402	7.520	6	0.195	0.313	7.402	7.520
7	0.176	0.290	7.386	7.500	7	0.192	0.314	7.398	7.521	7	0.192	0.314	7.398	7.521
8	0.382	0.290	7.592	7.499	8	0.416	0.314	7.623	7.521	8	0.416	0.314	7.623	7.521
9	0.372	0.267	7.582	7.477	9	0.404	0.290	7.611	7.497	9	0.404	0.290	7.611	7.497
10	0.344	0.000	7.554	7.209	10	0.374	-0.001	7.581	7.206	10	0.374	-0.001	7.581	7.206
11	0.319	0.267	7.528	7.477	11	0.346	0.290	7.553	7.497	11	0.346	0.290	7.553	7.497
12	0.263		7.472		12	0.285		7.492		12	0.285		7.492	
RPM=520	H=51.85	P=49.67	P (psi) = 7.204				RPM=540	H=52.03	P=49.66	P (psi) = 7.202				
Mon	May		9	15:36:01	1994		Mon	May		9	15:38:03	1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	0.000	7.204	7.203	1	0.000	0.000	7.202	7.202	1	0.000	0.000	7.202	7.202
2	0.030	0.030	7.234	7.234	2	0.030	0.030	7.233	7.232	2	0.030	0.030	7.233	7.232
3	0.226	0.140	7.430	7.344	3	0.245	0.152	7.447	7.354	3	0.245	0.152	7.447	7.354
4	0.220	0.124	7.424	7.327	4	0.239	0.134	7.442	7.336	4	0.239	0.134	7.442	7.336
5	0.216	0.166	7.420	7.370	5	0.234	0.180	7.436	7.382	5	0.234	0.180	7.436	7.382
6	0.213	0.342	7.417	7.545	6	0.231	0.370	7.433	7.572	6	0.231	0.370	7.433	7.572
7	0.209	0.342	7.413	7.546	7	0.226	0.371	7.429	7.574	7	0.226	0.371	7.429	7.574
8	0.454	0.342	7.658	7.546	8	0.493	0.371	7.695	7.573	8	0.493	0.371	7.695	7.573
9	0.441	0.316	7.645	7.520	9	0.479	0.343	7.681	7.546	9	0.479	0.343	7.681	7.546
10	0.407	-0.001	7.611	7.203	10	0.442	-0.001	7.644	7.202	10	0.442	-0.001	7.644	7.202
11	0.377	0.316	7.581	7.520	11	0.408	0.343	7.610	7.546	11	0.408	0.343	7.610	7.546
12	0.310		7.514		12	0.334		7.536		12	0.334		7.536	

RPM=560				RPM=580			
Mon	H=52.20	P=49.63	P (psi) = 7.198	Mon	H=52.38	P=49.62	P (psi) = 7.197
	May	9 15:40:28	1994		May	9 15:42:41	1994
Transducer	sc-01	sc-02	Average (psid)	Transducer	sc-01	sc-02	Average (psia)
1	0.000	-0.001	7.198	1	0.000	-0.001	7.196
2	0.030	0.030	7.228	2	0.030	0.030	7.227
3	0.266	0.164	7.463	3	0.286	0.178	7.483
4	0.259	0.145	7.457	4	0.279	0.157	7.476
5	0.254	0.196	7.452	5	0.274	0.211	7.470
6	0.250	0.399	7.448	6	0.270	0.432	7.467
7	0.246	0.401	7.444	7	0.264	0.434	7.461
8	0.533	0.401	7.731	8	0.575	0.434	7.772
9	0.518	0.372	7.716	9	0.560	0.403	7.757
10	0.478	-0.001	7.676	10	0.517	0.000	7.713
11	0.442	0.371	7.640	11	0.477	0.402	7.674
12	0.362		7.560	12	0.391		7.588
RPM=600				RPM=620			
Mon	H=52.63	P=49.66	P (psi) = 7.202	Mon	H=52.85	P=49.66	P (psi) = 7.202
	May	9 15:46:11	1994		May	9 15:49:00	1994
Transducer	sc-01	sc-02	Average (psid)	Transducer	sc-01	sc-02	Average (psia)
1	0.000	0.000	7.202	1	0.000	0.000	7.202
2	0.030	0.030	7.233	2	0.030	0.030	7.233
3	0.307	0.191	7.509	3	0.330	0.205	7.532
4	0.299	0.169	7.501	4	0.321	0.181	7.523
5	0.293	0.226	7.496	5	0.315	0.243	7.517
6	0.290	0.464	7.492	6	0.311	0.498	7.513
7	0.284	0.465	7.486	7	0.304	0.499	7.507
8	0.618	0.464	7.821	8	0.665	0.499	7.867
9	0.601	0.433	7.803	9	0.646	0.465	7.848
10	0.554	0.000	7.756	10	0.595	0.000	7.797
11	0.511	0.432	7.714	11	0.549	0.464	7.751
12	0.420		7.622	12	0.448		7.651
RPM=640				RPM=660			
Mon	H=53.08	P=49.66	P (psi) = 7.202	Mon	H=53.31	P=49.62	P (psi) = 7.197
	May	9 15:52:00	1994		May	9 15:54:35	1994
Transducer	sc-01	sc-02	Average (psid)	Transducer	sc-01	sc-02	Average (psia)
1	0.000	0.000	7.203	1	0.000	0.000	7.197
2	0.030	0.030	7.233	2	0.030	0.030	7.227
3	0.354	0.221	7.556	3	0.379	0.237	7.575
4	0.344	0.195	7.546	4	0.368	0.210	7.565
5	0.337	0.261	7.539	5	0.361	0.281	7.558
6	0.332	0.533	7.534	6	0.356	0.572	7.552
7	0.325	0.535	7.527	7	0.349	0.574	7.546
8	0.712	0.535	7.915	8	0.764	0.574	7.960
9	0.692	0.498	7.894	9	0.743	0.535	7.939
10	0.637	0.000	7.840	10	0.683	0.000	7.879
11	0.588	0.498	7.790	11	0.630	0.535	7.826
12	0.479		7.681	12	0.514		7.710
RPM=680				RPM=700			
Mon	H=53.50	P=49.62	P (psi) = 7.197	Mon	H=53.72	P=49.67	P (psi) = 7.204
	May	9 15:56:52	1994		May	9 15:59:12	1994
Transducer	sc-01	sc-02	Average (psid)	Transducer	sc-01	sc-02	Average (psia)
1	0.000	0.000	7.197	1	0.000	0.000	7.204
2	0.030	0.030	7.227	2	0.030	0.030	7.234
3	0.399	0.249	7.596	3	0.426	0.266	7.630
4	0.389	0.221	7.585	4	0.416	0.235	7.620
5	0.381	0.295	7.578	5	0.409	0.315	7.613
6	0.375	0.603	7.572	6	0.403	0.643	7.607
7	0.370	0.605	7.566	7	0.395	0.645	7.598
8	0.808	0.605	8.004	8	0.863	0.644	8.067
9	0.784	0.565	7.981	9	0.837	0.603	8.040
10	0.722	0.000	7.919	10	0.770	0.000	7.974
11	0.666	0.564	7.862	11	0.709	0.602	7.913
12	0.543		7.739	12	0.576		7.780

RPM=720				RPM=740				
Mon	H=53.98	P=49.55	P (psi) = 7.186	Mon	H=54.17	P=49.50	P (psi) = 7.179	
	May	9	16:02:07		May	9	16:04:07	
Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	
sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.000	0.000	7.186	7.186	0.000	0.000	7.179	7.179
2	0.030	0.030	7.217	7.217	0.030	0.030	7.210	7.210
3	0.454	0.285	7.641	7.471	0.478	0.299	7.657	7.478
4	0.444	0.253	7.630	7.439	0.465	0.266	7.644	7.445
5	0.436	0.338	7.622	7.524	0.455	0.355	7.634	7.534
6	0.430	0.688	7.617	7.874	0.447	0.723	7.627	7.902
7	0.422	0.689	7.609	7.875	0.439	0.725	7.618	7.904
8	0.921	0.688	8.107	7.875	0.964	0.724	8.143	7.903
9	0.893	0.644	8.080	7.830	0.940	0.678	8.119	7.857
10	0.822	0.000	8.008	7.186	0.864	0.000	8.043	7.179
11	0.757	0.643	7.943	7.830	0.795	0.677	7.974	7.856
12	0.615		7.801		0.647		7.827	
RPM=760				RPM=780				
Mon	H=54.40	P=49.44	P (psi) = 7.170	Mon	H=54.67	P=49.40	P (psi) = 7.165	
	May	9	16:06:31		May	9	16:09:01	
Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	
sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.000	0.000	7.171	7.170	0.000	0.000	7.165	7.164
2	0.030	0.030	7.201	7.201	0.031	0.031	7.195	7.195
3	0.507	0.319	7.677	7.489	0.538	0.339	7.702	7.504
4	0.493	0.283	7.663	7.453	0.524	0.301	7.689	7.466
5	0.483	0.378	7.653	7.548	0.515	0.402	7.680	7.567
6	0.476	0.765	7.646	7.936	0.507	0.814	7.672	7.979
7	0.467	0.767	7.637	7.938	0.499	0.816	7.663	7.981
8	1.021	0.767	8.191	7.937	1.085	0.815	8.250	7.980
9	0.993	0.719	8.164	7.889	1.059	0.765	8.223	7.930
10	0.912	0.000	8.082	7.171	0.971	0.000	8.135	7.165
11	0.841	0.718	8.011	7.888	0.895	0.764	8.059	7.929
12	0.683		7.853		0.727		7.892	
RPM=800				RPM=820				
Mon	H=54.93	P=49.40	P (psi) = 7.165	Mon	H=55.27	P=49.41	P (psi) = 7.166	
	May	9	16:11:48		May	9	16:15:51	
Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	
sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.000	0.000	7.165	7.165	0.001	0.000	7.167	7.166
2	0.031	0.030	7.195	7.195	0.031	0.030	7.197	7.196
3	0.565	0.356	7.730	7.521	0.600	0.380	7.766	7.546
4	0.548	0.316	7.713	7.481	0.583	0.339	7.750	7.505
5	0.537	0.422	7.702	7.587	0.571	0.450	7.737	7.616
6	0.529	0.854	7.693	8.018	0.562	0.906	7.728	8.072
7	0.521	0.856	7.685	8.021	0.553	0.909	7.719	8.075
8	1.137	0.855	8.301	8.019	1.206	0.908	8.372	8.074
9	1.110	0.803	8.274	7.968	1.178	0.853	8.344	8.019
10	1.017	0.000	8.181	7.165	1.080	0.000	8.246	7.166
11	0.937	0.802	8.102	7.967	0.995	0.852	8.161	8.018
12	0.760		7.924		0.805		7.971	
RPM=840				RPM=860				
Mon	H=55.54	P=49.38	P (psi) = 7.162	Mon	H=55.82	P=49.31	P (psi) = 7.152	
	May	9	16:18:36		May	9	16:20:47	
Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	Average (psia)	Transducer	Average (psid)	
sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.001	0.000	7.162	7.162	0.001	0.000	7.152	7.152
2	0.031	0.031	7.193	7.192	0.031	0.031	7.183	7.182
3	0.632	0.400	7.794	7.562	0.663	0.421	7.814	7.573
4	0.614	0.355	7.776	7.517	0.647	0.374	7.798	7.526
5	0.601	0.473	7.762	7.635	0.634	0.498	7.785	7.649
6	0.591	0.951	7.753	8.113	0.624	1.000	7.775	8.151
7	0.581	0.954	7.743	8.116	0.614	1.003	7.765	8.154
8	1.266	0.953	8.428	8.115	1.334	1.002	8.486	8.153
9	1.238	0.896	8.400	8.058	1.306	0.943	8.457	8.094
10	1.134	0.000	8.296	7.162	1.196	0.000	8.348	7.152
11	1.044	0.895	8.205	8.057	1.100	0.942	8.251	8.093
12	0.843		8.005		0.887		8.039	

RPM=880    H=56.08    P=49.25    P (psi) = 7.143				RPM=900    H=56.33    P=49.19    P (psi) = 7.134			
Mon	May	9	16:23:13	Mon	May	9	16:25:10
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.001	0.000	7.144	7.143	1	0.001	0.000
2	0.031	0.031	7.174	7.174	2	0.031	0.031
3	0.699	0.444	7.842	7.587	3	0.731	0.465
4	0.681	0.394	7.823	7.537	4	0.710	0.413
5	0.666	0.524	7.809	7.667	5	0.697	0.550
6	0.656	1.052	7.799	8.195	6	0.685	1.101
7	0.646	1.055	7.788	8.198	7	0.673	1.105
8	1.404	1.054	8.547	8.197	8	1.468	1.103
9	1.372	0.993	8.515	8.136	9	1.439	1.040
10	1.257	0.000	8.400	7.143	10	1.317	0.000
11	1.155	0.991	8.298	8.134	11	1.209	1.038
12	0.931		8.074		12	0.973	8.107
RPM=920    H=56.65    P=49.15    P (psi) = 7.128				RPM=940    H=56.92    P=49.11    P (psi) = 7.123			
Mon	May	9	16:28:01	Mon	May	9	16:30:09
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.001	0.000	7.129	7.129	1	0.001	0.000
2	0.032	0.031	7.160	7.159	2	0.032	0.031
3	0.763	0.486	7.892	7.614	3	0.789	0.503
4	0.743	0.432	7.871	7.560	4	0.766	0.448
5	0.728	0.574	7.857	7.703	5	0.751	0.594
6	0.716	1.152	7.845	8.281	6	0.739	1.198
7	0.703	1.156	7.832	8.285	7	0.726	1.202
8	1.530	1.155	8.658	8.283	8	1.589	1.201
9	1.501	1.089	8.630	8.218	9	1.563	1.133
10	1.375	0.000	8.503	7.129	10	1.430	0.000
11	1.263	1.088	8.391	8.217	11	1.314	1.132
12	1.015		8.144		12	1.058	8.181
RPM=960    H=57.19    P=49.05    P (psi) = 7.114				RPM=980    H=57.52    P=48.99    P (psi) = 7.105			
Mon	May	9	16:32:21	Mon	May	9	16:34:46
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.001	0.000	7.115	7.114	1	0.001	0.001
2	0.032	0.031	7.146	7.145	2	0.032	0.031
3	0.823	0.526	7.937	7.640	3	0.864	0.551
4	0.800	0.470	7.914	7.584	4	0.840	0.491
5	0.784	0.621	7.898	7.735	5	0.824	0.650
6	0.772	1.251	7.886	8.365	6	0.811	1.311
7	0.759	1.255	7.873	8.369	7	0.795	1.315
8	1.653	1.253	8.766	8.367	8	1.733	1.314
9	1.635	1.184	8.748	8.298	9	1.712	1.241
10	1.495	0.000	8.609	7.114	10	1.568	0.000
11	1.374	1.182	8.488	8.296	11	1.440	1.240
12	1.103		8.217		12	1.156	8.262
RPM=1000    H=57.82    P=48.90    P (psi) = 7.092				RPM=1020    H=58.14    P=48.82    P (psi) = 7.080			
Mon	May	9	16:36:46	Mon	May	9	16:38:54
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.002	0.001	7.094	7.093	1	0.001	0.001
2	0.032	0.031	7.124	7.123	2	0.032	0.031
3	0.900	0.575	7.992	7.667	3	0.944	0.603
4	0.875	0.514	7.967	7.606	4	0.915	0.537
5	0.860	0.679	7.952	7.771	5	0.898	0.710
6	0.848	1.367	7.940	8.459	6	0.881	1.428
7	0.831	1.371	7.923	8.464	7	0.865	1.431
8	1.799	1.370	8.891	8.462	8	1.867	1.430
9	1.787	1.296	8.879	8.388	9	1.862	1.353
10	1.637	0.001	8.729	7.093	10	1.708	0.001
11	1.500	1.294	8.593	8.386	11	1.566	1.351
12	1.204		8.296		12	1.256	8.337

RPM=1040 H=58.48 P=48.80 P (psi) = 7.078				RPM=1060 H=58.81 P=48.77 P (psi) = 7.073			
Mon	May	9	16:41:58	Mon	May	9	16:43:46
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.002	0.001	7.079	7.078	1	0.002	0.001
2	0.032	0.032	7.110	7.109	2	0.032	0.032
3	0.977	0.623	8.054	7.701	3	1.013	0.649
4	0.947	0.555	8.024	7.632	4	0.986	0.578
5	0.929	0.735	8.006	7.812	5	0.966	0.765
6	0.914	1.479	7.991	8.557	6	0.949	1.541
7	0.895	1.483	7.972	8.560	7	0.932	1.544
8	1.933	1.481	9.011	8.559	8	2.015	1.542
9	1.939	1.402	9.017	8.480	9	2.017	1.461
10	1.776	0.001	8.854	7.078	10	1.844	0.001
11	1.624	1.400	8.702	8.478	11	1.688	1.460
12	1.298		8.375		12	1.356	8.429
RPM=1080 H=59.17 P=48.70 P (psi) = 7.063				RPM=1100 H=59.39 P=48.54 P (psi) = 7.040			
Mon	May	9	16:46:29	Mon	May	9	16:48:00
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.002	0.001	7.065	7.064	1	0.002	0.001
2	0.032	0.032	7.095	7.095	2	0.033	0.032
3	1.053	0.677	8.117	7.740	3	1.093	0.703
4	1.023	0.604	8.086	7.668	4	1.061	0.628
5	1.002	0.796	8.065	7.859	5	1.039	0.826
6	0.984	1.602	8.047	8.665	6	1.019	1.659
7	0.965	1.606	8.028	8.669	7	1.001	1.664
8	2.103	1.604	9.166	8.667	8	2.166	1.661
9	2.096	1.521	9.159	8.584	9	2.172	1.576
10	1.916	0.001	8.979	7.064	10	1.986	0.001
11	1.753	1.519	8.816	8.582	11	1.816	1.574
12	1.407		8.470		12	1.464	8.504
RPM=1120 H=59.74 P=48.40 P (psi) = 7.020				RPM=1140 H=60.13 P=48.44 P (psi) = 7.025			
Mon	May	9	16:50:13	Mon	May	9	16:53:41
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.002	0.001	7.022	7.021	1	0.002	0.001
2	0.033	0.032	7.053	7.052	2	0.033	0.032
3	1.136	0.732	8.156	7.751	3	1.184	0.763
4	1.101	0.654	8.120	7.673	4	1.146	0.683
5	1.077	0.861	8.097	7.880	5	1.121	0.898
6	1.059	1.728	8.079	8.748	6	1.100	1.799
7	1.039	1.732	8.058	8.752	7	1.082	1.804
8	2.260	1.730	9.279	8.750	8	2.360	1.801
9	2.264	1.641	9.283	8.661	9	2.349	1.710
10	2.067	0.001	9.086	7.021	10	2.148	0.001
11	1.892	1.640	8.912	8.659	11	1.965	1.709
12	1.523		8.543		12	1.584	8.610
RPM=1160 H=60.47 P=48.38 P (psi) = 7.017				RPM=0 H=56.06 P=56.08 P (psi) = 8.133			
Mon	May	9	16:55:21	Mon	May	9	17:00:38
Average (psid)				Average (psia)			
Transducer	sc-01	sc-02	sc-01	sc-02	Transducer	sc-01	sc-02
1	0.002	0.002	7.019	7.018	1	0.001	0.000
2	0.033	0.032	7.049	7.049	2	0.025	0.024
3	1.219	0.789	8.235	7.806	3	0.002	0.001
4	1.181	0.706	8.197	7.722	4	0.001	0.001
5	1.157	0.928	8.174	7.945	5	0.000	0.001
6	1.138	1.855	8.155	8.872	6	0.001	0.000
7	1.116	1.861	8.133	8.878	7	0.001	0.001
8	2.421	1.859	9.437	8.876	8	0.002	0.000
9	2.430	1.766	9.447	8.783	9	0.001	0.001
10	2.221	0.001	9.237	7.018	10	0.001	0.000
11	2.028	1.764	9.044	8.781	11	0.001	0.001
12	1.638		8.655		12	0.000	8.134

DSTO-TN-0150

## **A.2 Pressure Data - Nozzle 2 - Incremental (N2 INCR)**

DSTO-TN-0150

RPM=0 Wed	H=48.09 May	P=48.09 11	P (psi) = 6.975 13:58:49 1994	RPM=400 Wed	H=49.22 May	P=48.11 11	P (psi) = 6.978 14:04:55 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	-0.001	6.974	6.974	1	0.000	-0.001	6.977	6.977
2	0.029	0.030	7.004	7.004	2	0.029	0.030	7.007	7.007
3	0.000	-0.001	6.974	6.974	3	0.110	0.063	7.088	7.040
4	-0.001	0.000	6.974	6.974	4	0.107	0.054	7.085	7.031
5	-0.001	-0.001	6.974	6.974	5	0.105	0.076	7.083	7.054
6	-0.001	0.000	6.974	6.975	6	0.104	0.175	7.081	7.152
7	0.000	-0.001	6.975	6.974	7	0.102	0.175	7.080	7.152
8	-0.001	0.000	6.974	6.975	8	0.234	0.174	7.211	7.152
9	-0.001	-0.001	6.974	6.974	9	0.228	0.158	7.205	7.135
10	-0.001	-0.001	6.974	6.974	10	0.211	-0.001	7.188	6.977
11	-0.001	-0.001	6.974	6.974	11	0.193	0.158	7.171	7.135
12	-0.001		6.974		12	0.157		7.135	
RPM=420 Wed	H=49.41 May	P=48.20 11	P (psi) = 6.991 14:07:49 1994	RPM=440 Wed	H=49.58 May	P=48.23 11	P (psi) = 6.995 14:10:13 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	-0.001	6.990	6.990	1	0.000	-0.001	6.995	6.994
2	0.029	0.030	7.020	7.020	2	0.029	0.030	7.024	7.025
3	0.124	0.070	7.114	7.061	3	0.137	0.079	7.132	7.074
4	0.120	0.060	7.110	7.051	4	0.133	0.067	7.128	7.062
5	0.118	0.086	7.108	7.076	5	0.131	0.096	7.126	7.091
6	0.116	0.194	7.107	7.184	6	0.129	0.214	7.124	7.209
7	0.115	0.194	7.105	7.184	7	0.127	0.215	7.122	7.210
8	0.260	0.193	7.251	7.184	8	0.290	0.215	7.284	7.210
9	0.254	0.176	7.244	7.166	9	0.282	0.195	7.277	7.190
10	0.234	-0.001	7.225	6.990	10	0.260	-0.001	7.255	6.994
11	0.215	0.175	7.205	7.166	11	0.239	0.195	7.233	7.190
12	0.175		7.165		12	0.193		7.188	
RPM=460 Wed	H=49.72 May	P=48.25 11	P (psi) = 6.998 14:12:17 1994	RPM=480 Wed	H=49.92 May	P=48.29 11	P (psi) = 7.004 14:15:25 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	-0.001	6.998	6.997	1	0.000	-0.001	7.003	7.003
2	0.029	0.030	7.027	7.027	2	0.029	0.029	7.033	7.033
3	0.151	0.086	7.149	7.084	3	0.167	0.095	7.171	7.099
4	0.147	0.074	7.145	7.072	4	0.162	0.082	7.166	7.085
5	0.145	0.105	7.142	7.103	5	0.160	0.116	7.163	7.120
6	0.143	0.235	7.141	7.233	6	0.158	0.258	7.161	7.262
7	0.141	0.235	7.138	7.233	7	0.155	0.259	7.159	7.262
8	0.318	0.235	7.316	7.233	8	0.352	0.259	7.355	7.262
9	0.309	0.214	7.306	7.212	9	0.341	0.237	7.345	7.240
10	0.285	-0.001	7.283	6.997	10	0.314	-0.001	7.318	7.003
11	0.261	0.214	7.259	7.212	11	0.288	0.237	7.292	7.240
12	0.211		7.209		12	0.232		7.236	
RPM=500 Wed	H=50.09 May	P=48.31 11	P (psi) = 7.007 14:17:50 1994	RPM=520 Wed	H=50.27 May	P=48.33 11	P (psi) = 7.009 14:20:29 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	-0.001	7.006	7.006	1	0.000	-0.001	7.009	7.009
2	0.029	0.029	7.036	7.036	2	0.029	0.029	7.039	7.039
3	0.184	0.104	7.190	7.111	3	0.199	0.113	7.209	7.123
4	0.178	0.090	7.185	7.096	4	0.194	0.098	7.203	7.107
5	0.175	0.128	7.182	7.135	5	0.191	0.139	7.200	7.149
6	0.173	0.283	7.179	7.290	6	0.187	0.307	7.197	7.317
7	0.170	0.284	7.177	7.290	7	0.185	0.308	7.195	7.317
8	0.387	0.283	7.394	7.290	8	0.420	0.307	7.430	7.317
9	0.375	0.260	7.381	7.267	9	0.406	0.282	7.416	7.291
10	0.344	-0.001	7.351	7.006	10	0.373	-0.001	7.382	7.009
11	0.316	0.260	7.323	7.266	11	0.343	0.281	7.352	7.291
12	0.255		7.261		12	0.275		7.284	

RPM=540	H=50.47	P=48.37	P (psi) = 7.015	RPM=560	H=50.66	P=48.38	P (psi) = 7.017		
Wed	May	11	14:23:31	1994	Wed	May	11	14:26:15	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	-0.001	7.015	7.015	1	0.000	-0.001	7.017	7.016
2	0.029	0.029	7.044	7.045	2	0.029	0.029	7.046	7.046
3	0.215	0.123	7.230	7.138	3	0.234	0.134	7.250	7.150
4	0.209	0.106	7.224	7.121	4	0.228	0.115	7.245	7.132
5	0.206	0.151	7.221	7.166	5	0.224	0.164	7.241	7.181
6	0.202	0.332	7.217	7.347	6	0.220	0.360	7.237	7.377
7	0.199	0.333	7.214	7.348	7	0.217	0.361	7.234	7.378
8	0.455	0.332	7.470	7.348	8	0.493	0.360	7.510	7.377
9	0.440	0.305	7.455	7.320	9	0.477	0.331	7.494	7.348
10	0.403	-0.001	7.418	7.015	10	0.438	0.000	7.454	7.016
11	0.370	0.305	7.386	7.320	11	0.402	0.331	7.418	7.348
12	0.297		7.313		12	0.322		7.339	
RPM=580	H=50.85	P=48.39	P (psi) = 7.018	RPM=600	H=51.05	P=48.38	P (psi) = 7.017		
Wed	May	11	14:28:49	1994	Wed	May	11	14:31:20	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	0.000	7.018	7.018	1	0.000	0.000	7.017	7.016
2	0.029	0.029	7.047	7.047	2	0.029	0.029	7.046	7.046
3	0.253	0.145	7.271	7.163	3	0.269	0.155	7.286	7.172
4	0.247	0.125	7.265	7.143	4	0.263	0.134	7.280	7.150
5	0.242	0.178	7.260	7.196	5	0.259	0.191	7.276	7.208
6	0.238	0.387	7.256	7.406	6	0.255	0.417	7.272	7.433
7	0.235	0.389	7.253	7.407	7	0.251	0.418	7.268	7.434
8	0.533	0.389	7.551	7.407	8	0.570	0.418	7.587	7.435
9	0.516	0.358	7.534	7.376	9	0.552	0.385	7.569	7.402
10	0.474	0.000	7.492	7.018	10	0.507	0.000	7.523	7.016
11	0.434	0.358	7.452	7.376	11	0.464	0.385	7.481	7.401
12	0.349		7.367		12	0.372		7.389	
RPM=620	H=51.22	P=48.38	P (psi) = 7.017	RPM=640	H=51.42	P=48.36	P (psi) = 7.014		
Wed	May	11	14:33:22	1994	Wed	May	11	14:35:51	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	0.000	7.017	7.016	1	0.000	0.000	7.014	7.013
2	0.029	0.029	7.046	7.046	2	0.029	0.029	7.043	7.043
3	0.289	0.165	7.305	7.182	3	0.313	0.179	7.327	7.193
4	0.281	0.142	7.298	7.159	4	0.303	0.155	7.317	7.168
5	0.276	0.203	7.293	7.220	5	0.298	0.219	7.312	7.233
6	0.272	0.445	7.289	7.462	6	0.294	0.479	7.308	7.493
7	0.267	0.446	7.284	7.463	7	0.289	0.480	7.302	7.494
8	0.613	0.446	7.630	7.463	8	0.661	0.479	7.675	7.493
9	0.592	0.412	7.608	7.428	9	0.639	0.444	7.653	7.458
10	0.542	0.000	7.559	7.016	10	0.584	0.000	7.598	7.014
11	0.497	0.411	7.513	7.428	11	0.535	0.443	7.548	7.457
12	0.396		7.413		12	0.426		7.439	
RPM=660	H=51.62	P=48.36	P (psi) = 7.014	RPM=680	H=51.83	P=48.36	P (psi) = 7.014		
Wed	May	11	14:38:13	1994	Wed	May	11	14:40:39	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
1	0.000	-0.001	7.014	7.013	1	0.000	0.000	7.014	7.014
2	0.029	0.029	7.043	7.043	2	0.029	0.029	7.043	7.043
3	0.334	0.192	7.348	7.205	3	0.353	0.203	7.367	7.217
4	0.325	0.166	7.339	7.179	4	0.343	0.175	7.357	7.189
5	0.319	0.235	7.333	7.249	5	0.337	0.249	7.351	7.263
6	0.315	0.513	7.329	7.527	6	0.332	0.542	7.345	7.556
7	0.309	0.514	7.323	7.528	7	0.325	0.544	7.338	7.557
8	0.708	0.513	7.722	7.527	8	0.748	0.543	7.762	7.557
9	0.685	0.475	7.699	7.489	9	0.722	0.503	7.736	7.517
10	0.626	0.000	7.639	7.013	10	0.661	0.000	7.675	7.014
11	0.572	0.474	7.586	7.488	11	0.604	0.502	7.618	7.516
12	0.455		7.469		12	0.481		7.494	

RPM=700	H=52.04	P=48.33	P (psi) = 7.009		RPM=720	H=52.34	P=48.42	P (psi) = 7.022	
Wed	May	11	14:43:03	1994	Wed	May	11	14:47:08	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	0.000	7.009	7.009	1	0.000	0.000	7.023	7.022
2	0.029	0.029	7.039	7.039	2	0.029	0.029	7.052	7.052
3	0.378	0.217	7.388	7.227	3	0.399	0.230	7.421	7.253
4	0.368	0.187	7.377	7.196	4	0.388	0.198	7.410	7.221
5	0.362	0.267	7.371	7.276	5	0.381	0.282	7.404	7.305
6	0.356	0.580	7.365	7.589	6	0.374	0.614	7.397	7.637
7	0.350	0.581	7.360	7.590	7	0.368	0.616	7.390	7.638
8	0.802	0.581	7.812	7.590	8	0.847	0.616	7.869	7.638
9	0.773	0.538	7.783	7.548	9	0.818	0.571	7.841	7.593
10	0.708	0.000	7.718	7.009	10	0.749	0.000	7.771	7.022
11	0.646	0.538	7.656	7.547	11	0.684	0.570	7.706	7.593
12	0.512		7.522		12	0.543		7.565	
RPM=740	H=52.63	P=48.40	P (psi) = 7.020		RPM=760	H=52.92	P=48.47	P (psi) = 7.030	
Wed	May	11	14:50:16	1994	Wed	May	11	14:54:07	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	0.000	7.020	7.019	1	0.000	0.000	7.030	7.030
2	0.029	0.029	7.049	7.049	2	0.029	0.029	7.059	7.059
3	0.423	0.245	7.443	7.265	3	0.451	0.262	7.481	7.292
4	0.413	0.211	7.433	7.231	4	0.440	0.226	7.470	7.256
5	0.405	0.300	7.425	7.320	5	0.432	0.321	7.462	7.350
6	0.398	0.651	7.418	7.670	6	0.426	0.693	7.456	7.723
7	0.392	0.653	7.411	7.672	7	0.419	0.695	7.449	7.725
8	0.899	0.652	7.918	7.671	8	0.955	0.694	7.985	7.724
9	0.869	0.606	7.889	7.626	9	0.925	0.645	7.954	7.675
10	0.795	0.000	7.815	7.020	10	0.846	0.000	7.876	7.030
11	0.725	0.605	7.745	7.625	11	0.772	0.645	7.802	7.674
12	0.575		7.594		12	0.612		7.642	
RPM=780	H=53.17	P=48.49	P (psi) = 7.033		RPM=800	H=53.39	P=48.46	P (psi) = 7.028	
Wed	May	11	14:57:02	1994	Wed	May	11	14:59:20	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	0.000	7.033	7.032	1	0.000	0.000	7.029	7.028
2	0.029	0.029	7.062	7.062	2	0.029	0.029	7.057	7.058
3	0.474	0.275	7.506	7.308	3	0.499	0.292	7.527	7.320
4	0.461	0.238	7.493	7.270	4	0.486	0.252	7.515	7.280
5	0.452	0.337	7.485	7.370	5	0.479	0.357	7.507	7.386
6	0.444	0.728	7.477	7.760	6	0.471	0.768	7.499	7.797
7	0.436	0.730	7.469	7.762	7	0.461	0.771	7.490	7.799
8	1.001	0.729	8.034	7.762	8	1.057	0.770	8.086	7.798
9	0.972	0.678	8.005	7.711	9	1.027	0.718	8.055	7.746
10	0.886	0.000	7.919	7.033	10	0.937	0.000	7.965	7.028
11	0.808	0.677	7.841	7.710	11	0.855	0.717	7.883	7.745
12	0.639		7.672		12	0.678		7.706	
RPM=820	H=53.65	P=48.43	P (psi) = 7.024		RPM=840	H=53.91	P=48.42	P (psi) = 7.022	
Wed	May	11	15:01:42	1994	Wed	May	11	15:04:17	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	0.000	7.024	7.024	1	0.000	0.000	7.023	7.023
2	0.029	0.029	7.053	7.053	2	0.029	0.029	7.052	7.052
3	0.525	0.307	7.549	7.331	3	0.556	0.325	7.579	7.348
4	0.511	0.266	7.535	7.290	4	0.541	0.282	7.563	7.304
5	0.504	0.376	7.527	7.400	5	0.532	0.398	7.554	7.421
6	0.495	0.809	7.519	7.833	6	0.523	0.853	7.546	7.876
7	0.487	0.811	7.511	7.835	7	0.514	0.855	7.537	7.877
8	1.115	0.811	8.139	7.835	8	1.177	0.854	8.199	7.876
9	1.081	0.756	8.105	7.780	9	1.141	0.797	8.163	7.820
10	0.987	0.000	8.011	7.024	10	1.041	0.000	8.064	7.023
11	0.900	0.755	7.924	7.779	11	0.948	0.796	7.971	7.818
12	0.711		7.735		12	0.749		7.772	

RPM=860 H=54.17 P=48.38 11 15:06:52 1994				RPM=880 H=54.46 P=48.37 11 15:09:39 1994			
Transducer	Average (psid) sc-01	Average (psia) sc-02	Average (psid) sc-01	Average (psia) sc-02	Transducer	Average (psid) sc-01	Average (psia) sc-02
1	0.001	0.000	7.017	7.017	1	0.000	0.000
2	0.029	0.029	7.046	7.046	2	0.029	0.029
3	0.584	0.343	7.601	7.359	3	0.615	0.362
4	0.569	0.297	7.586	7.313	4	0.598	0.312
5	0.561	0.419	7.577	7.436	5	0.588	0.442
6	0.551	0.897	7.568	7.913	6	0.577	0.945
7	0.541	0.899	7.558	7.916	7	0.568	0.946
8	1.238	0.898	8.254	7.915	8	1.302	0.945
9	1.203	0.839	8.220	7.855	9	1.264	0.883
10	1.096	0.000	8.113	7.017	10	1.152	0.000
11	0.997	0.838	8.013	7.855	11	1.047	0.882
12	0.784		7.801		12	0.824	7.839
RPM=900 H=54.76 P=48.36 11 15:12:03 1994				RPM=920 H=55.11 P=48.43 11 15:15:43 1994			
Transducer	Average (psid) sc-01	Average (psia) sc-02	Average (psid) sc-01	Average (psia) sc-02	Transducer	Average (psid) sc-01	Average (psia) sc-02
1	0.000	0.000	7.014	7.014	1	0.001	0.000
2	0.029	0.029	7.043	7.043	2	0.029	0.030
3	0.645	0.380	7.659	7.394	3	0.668	0.393
4	0.628	0.328	7.642	7.342	4	0.650	0.339
5	0.618	0.464	7.632	7.478	5	0.638	0.480
6	0.607	0.993	7.621	8.007	6	0.626	1.029
7	0.596	0.995	7.610	8.009	7	0.613	1.031
8	1.368	0.995	8.382	8.008	8	1.412	1.029
9	1.331	0.930	8.345	7.943	9	1.377	0.964
10	1.214	0.000	8.228	7.014	10	1.256	0.000
11	1.103	0.929	8.117	7.943	11	1.140	0.963
12	0.865		7.879		12	0.895	7.919
RPM=940 H=55.46 P=48.43 11 15:19:15 1994				RPM=960 H=55.71 P=48.42 11 15:21:18 1994			
Transducer	Average (psid) sc-01	Average (psia) sc-02	Average (psid) sc-01	Average (psia) sc-02	Transducer	Average (psid) sc-01	Average (psia) sc-02
1	0.001	0.000	7.025	7.024	1	0.001	0.000
2	0.029	0.029	7.053	7.053	2	0.030	0.030
3	0.700	0.414	7.724	7.438	3	0.727	0.429
4	0.681	0.359	7.705	7.383	4	0.705	0.372
5	0.669	0.506	7.693	7.530	5	0.692	0.524
6	0.657	1.086	7.681	8.110	6	0.679	1.127
7	0.644	1.089	7.668	8.113	7	0.664	1.130
8	1.494	1.087	8.517	8.111	8	1.545	1.128
9	1.456	1.018	8.479	8.042	9	1.509	1.057
10	1.325	0.000	8.349	7.024	10	1.374	0.001
11	1.205	1.017	8.228	8.041	11	1.248	1.056
12	0.943		7.967		12	0.975	7.997
RPM=980 H=56.04 P=48.41 11 15:24:02 1994				RPM=1000 H=56.38 P=48.43 11 15:27:06 1994			
Transducer	Average (psid) sc-01	Average (psia) sc-02	Average (psid) sc-01	Average (psia) sc-02	Transducer	Average (psid) sc-01	Average (psia) sc-02
1	0.001	0.001	7.022	7.022	1	0.001	0.001
2	0.029	0.030	7.051	7.051	2	0.030	0.030
3	0.764	0.452	7.785	7.473	3	0.793	0.470
4	0.744	0.391	7.765	7.412	4	0.770	0.408
5	0.731	0.552	7.752	7.573	5	0.757	0.574
6	0.717	1.182	7.738	8.203	6	0.744	1.229
7	0.702	1.185	7.723	8.206	7	0.729	1.232
8	1.626	1.184	8.647	8.205	8	1.682	1.231
9	1.586	1.110	8.607	8.131	9	1.649	1.155
10	1.444	0.001	8.465	7.022	10	1.503	0.001
11	1.312	1.109	8.333	8.130	11	1.362	1.155
12	1.025		8.046		12	1.061	8.085

RPM=1020	H=56.73	P=48.40	P (psi) = 7.020		RPM=1040	H=57.03	P=48.38	P (psi) = 7.017	
Wed	May	11	15:29:41	1994	Wed	May	11	15:32:12	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.001	0.001	7.021	7.020	1	0.001	0.001	7.018	7.017
2	0.030	0.030	7.049	7.049	2	0.030	0.030	7.047	7.047
3	0.830	0.492	7.850	7.512	3	0.861	0.510	7.878	7.527
4	0.807	0.427	7.827	7.446	4	0.838	0.441	7.855	7.458
5	0.794	0.600	7.814	7.620	5	0.823	0.622	7.840	7.638
6	0.779	1.283	7.799	8.302	6	0.808	1.333	7.825	8.349
7	0.760	1.286	7.780	8.306	7	0.790	1.336	7.807	8.352
8	1.746	1.284	8.766	8.304	8	1.816	1.334	8.833	8.351
9	1.724	1.207	8.744	8.226	9	1.797	1.254	8.814	8.270
10	1.574	0.001	8.593	7.020	10	1.637	0.001	8.654	7.017
11	1.425	1.205	8.444	8.225	11	1.481	1.253	8.497	8.269
12	1.112		8.132		12	1.152		8.168	
RPM=1060	H=57.36	P=48.34	P (psi) = 7.011		RPM=1080	H=57.65	P=48.27	P (psi) = 7.001	
Wed	May	11	15:34:41	1994	Wed	May	11	15:37:05	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.001	0.001	7.012	7.012	1	0.001	0.001	7.002	7.002
2	0.030	0.030	7.040	7.041	2	0.030	0.030	7.031	7.031
3	0.895	0.532	7.906	7.543	3	0.934	0.556	7.935	7.556
4	0.872	0.461	7.883	7.472	4	0.908	0.482	7.909	7.483
5	0.856	0.648	7.867	7.659	5	0.890	0.674	7.890	7.675
6	0.840	1.388	7.851	8.399	6	0.872	1.446	7.873	8.447
7	0.823	1.392	7.834	8.402	7	0.854	1.449	7.855	8.450
8	1.895	1.390	8.906	8.401	8	1.982	1.448	8.982	8.448
9	1.872	1.307	8.883	8.318	9	1.950	1.362	8.951	8.363
10	1.699	0.001	8.710	7.012	10	1.766	0.001	8.767	7.002
11	1.537	1.306	8.547	8.317	11	1.597	1.360	8.598	8.361
12	1.206		8.217		12	1.252		8.253	
RPM=1100	H=57.90	P=48.18	P (psi) = 6.988		RPM=1120	H=58.24	P=48.13	P (psi) = 6.980	
Wed	May	11	15:39:12	1994	Wed	May	11	15:41:44	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.001	0.001	6.989	6.989	1	0.001	0.001	6.982	6.982
2	0.030	0.030	7.017	7.017	2	0.030	0.030	7.010	7.010
3	0.966	0.578	7.954	7.565	3	1.006	0.603	7.987	7.583
4	0.938	0.501	7.926	7.489	4	0.977	0.522	7.957	7.502
5	0.920	0.701	7.907	7.689	5	0.957	0.731	7.937	7.712
6	0.903	1.496	7.891	8.484	6	0.939	1.559	7.920	8.540
7	0.883	1.501	7.871	8.489	7	0.920	1.563	7.901	8.543
8	2.033	1.500	9.021	8.487	8	2.125	1.560	9.106	8.540
9	2.021	1.412	9.009	8.400	9	2.105	1.470	9.085	8.451
10	1.832	0.001	8.820	6.989	10	1.908	0.001	8.888	6.982
11	1.655	1.411	8.643	8.398	11	1.728	1.469	8.708	8.450
12	1.300		8.288		12	1.355		8.336	
RPM=1140	H=58.61	P=48.10	P (psi) = 6.976		RPM=1160	H=58.91	P=48.01	P (psi) = 6.963	
Wed	May	11	15:44:28	1994	Wed	May	11	15:46:44	1994
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.001	0.001	6.978	6.977	1	0.001	0.001	6.964	6.964
2	0.030	0.030	7.006	7.006	2	0.030	0.030	6.993	6.993
3	1.037	0.623	8.013	7.599	3	1.081	0.651	8.044	7.614
4	1.006	0.540	7.982	7.516	4	1.047	0.565	8.011	7.528
5	0.984	0.756	7.960	7.732	5	1.026	0.789	7.989	7.752
6	0.965	1.607	7.941	8.583	6	1.007	1.680	7.970	8.643
7	0.946	1.612	7.922	8.588	7	0.988	1.684	7.951	8.647
8	2.185	1.609	9.161	8.585	8	2.278	1.681	9.241	8.645
9	2.167	1.518	9.143	8.494	9	2.266	1.586	9.229	8.549
10	1.965	0.001	8.941	6.977	10	2.060	0.001	9.023	6.964
11	1.778	1.517	8.754	8.493	11	1.858	1.585	8.821	8.548
12	1.395		8.371		12	1.453		8.416	

RPM=0 H=54.88 P=54.89 P (psi) = 7.961				RPM=0 H=55.11 P=55.11 P (psi) = 7.993					
Wed	May	11	15:50:26	Wed	May	11	15:56:55		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.000	0.000	7.961	7.960	1	0.000	-0.001	7.993	7.992
2	0.023	0.023	7.984	7.984	2	0.024	0.023	8.016	8.016
3	0.000	0.001	7.961	7.961	3	0.000	0.001	7.993	7.993
4	0.000	0.001	7.961	7.961	4	0.000	0.000	7.992	7.993
5	0.000	0.000	7.961	7.961	5	-0.001	0.000	7.992	7.992
6	0.000	0.000	7.961	7.961	6	0.000	0.000	7.993	7.993
7	0.000	0.001	7.961	7.961	7	0.000	0.000	7.993	7.993
8	0.000	0.000	7.960	7.961	8	0.000	-0.001	7.992	7.992
9	0.000	-0.001	7.961	7.960	9	-0.001	-0.001	7.992	7.992
10	0.000	0.000	7.961	7.961	10	0.000	0.000	7.993	7.992
11	0.000	0.001	7.961	7.961	11	0.000	0.001	7.992	7.993
12	0.000		7.961		12	0.000		7.992	

### **A.3 Pressure Data - Nozzle 3 - Incremental (N3 INCR)**



RPM=0	H=48.28	P=48.28	P (psi) = 7.002	RPM=400	H=48.75	P=47.84	P (psi) = 6.938		
Fri	May	13	13:50:42 1994	Fri	May	13	13:53:58 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02	1	0.000	0.000	6.939	6.938
1	0.000	-0.001	7.002	7.001	2	0.030	0.030	6.968	6.968
2	0.029	0.029	7.032	7.031	3	0.089	0.040	7.028	6.978
3	0.000	0.000	7.002	7.002	4	0.086	0.030	7.024	6.968
4	0.000	0.000	7.002	7.002	5	0.084	0.054	7.022	6.993
5	0.000	0.000	7.002	7.002	6	0.083	0.148	7.021	7.086
6	0.000	0.000	7.003	7.003	7	0.081	0.148	7.019	7.087
7	0.000	0.000	7.002	7.002	8	0.213	0.148	7.152	7.086
8	0.000	0.000	7.002	7.002	9	0.206	0.131	7.144	7.069
9	0.000	-0.001	7.002	7.001	10	0.187	0.000	7.126	6.938
10	0.000	0.000	7.002	7.002	11	0.169	0.131	7.108	7.069
11	0.000	0.000	7.002	7.002	12	0.130		7.068	
RPM=420	H=48.90	P=47.89	P (psi) = 6.946	RPM=440	H=49.00	P=47.89	P (psi) = 6.946		
Fri	May	13	13:56:26 1994	Fri	May	13	13:57:48 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02	1	0.000	0.000	6.946	6.945
1	0.000	0.000	6.946	6.945	2	0.030	0.030	6.975	6.975
2	0.030	0.030	6.975	6.975	3	0.110	0.049	7.055	6.994
3	0.100	0.044	7.045	6.990	4	0.105	0.037	7.051	6.982
4	0.096	0.033	7.042	6.979	5	0.102	0.067	7.048	7.013
5	0.094	0.061	7.039	7.007	6	0.101	0.181	7.047	7.126
6	0.093	0.164	7.038	7.110	7	0.098	0.181	7.044	7.127
7	0.091	0.165	7.036	7.111	8	0.263	0.181	7.209	7.126
8	0.239	0.165	7.184	7.110	9	0.252	0.161	7.198	7.106
9	0.229	0.146	7.175	7.091	10	0.229	0.000	7.175	6.945
10	0.209	0.000	7.155	6.945	11	0.207	0.161	7.152	7.106
11	0.189	0.146	7.134	7.091	12	0.158		7.103	
RPM=460	H=49.14	P=47.92	P (psi) = 6.950	RPM=480	H=49.31	P=47.95	P (psi) = 6.954		
Fri	May	13	14:00:02 1994	Fri	May	13	14:02:38 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02	1	0.000	0.000	6.955	6.954
1	0.000	-0.001	6.950	6.949	2	0.030	0.030	6.984	6.984
2	0.030	0.030	6.980	6.980	3	0.135	0.060	7.090	7.014
3	0.122	0.054	7.072	7.004	4	0.130	0.046	7.084	7.000
4	0.117	0.041	7.067	6.991	5	0.127	0.083	7.081	7.037
5	0.114	0.074	7.064	7.024	6	0.125	0.219	7.080	7.173
6	0.114	0.199	7.064	7.149	7	0.122	0.220	7.076	7.174
7	0.110	0.200	7.060	7.150	8	0.322	0.220	7.276	7.174
8	0.291	0.199	7.241	7.149	9	0.308	0.196	7.262	7.151
9	0.278	0.177	7.228	7.127	10	0.280	0.000	7.234	6.954
10	0.253	0.000	7.203	6.950	11	0.251	0.196	7.206	7.151
11	0.227	0.177	7.177	7.127	12	0.191		7.145	
RPM=500	H=49.48	P=48.00	P (psi) = 6.962	RPM=520	H=49.65	P=48.04	P (psi) = 6.967		
Fri	May	13	14:05:25 1994	Fri	May	13	14:08:03 1994		
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02	1	0.000	0.000	6.968	6.967
1	0.000	0.000	6.962	6.961	2	0.030	0.029	6.997	6.997
2	0.030	0.029	6.991	6.991	3	0.160	0.071	7.128	7.039
3	0.148	0.066	7.109	7.027	4	0.154	0.055	7.122	7.022
4	0.142	0.050	7.104	7.012	5	0.150	0.098	7.118	7.066
5	0.139	0.090	7.100	7.052	6	0.148	0.258	7.116	7.225
6	0.137	0.238	7.098	7.199	7	0.144	0.259	7.112	7.226
7	0.133	0.239	7.095	7.200	8	0.381	0.259	7.348	7.226
8	0.351	0.239	7.313	7.201	9	0.363	0.232	7.330	7.199
9	0.335	0.214	7.296	7.175	10	0.329	0.000	7.297	6.967
10	0.304	0.000	7.265	6.961	11	0.296	0.232	7.263	7.199
11	0.273	0.214	7.235	7.175	12	0.224		7.192	

RPM=540				RPM=560					
Fri	H=49.81	P=48.06	P (psi) = 6.970	Fri	H=49.95	P=48.06	P (psi) = 6.970		
Transducer	May 13		14:10:22 1994	Transducer	May 13		14:12:15 1994		
	Average (psid)		Average (psia)		Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.000	0.000	6.971	6.970	1	0.000	0.000	6.971	6.970
2	0.030	0.029	7.000	7.000	2	0.030	0.029	7.000	7.000
3	0.175	0.078	7.145	7.048	3	0.191	0.085	7.161	7.055
4	0.168	0.060	7.138	7.030	4	0.183	0.065	7.153	7.036
5	0.164	0.107	7.134	7.077	5	0.178	0.117	7.148	7.087
6	0.162	0.281	7.132	7.251	6	0.175	0.304	7.145	7.275
7	0.158	0.282	7.128	7.252	7	0.171	0.305	7.141	7.276
8	0.416	0.281	7.386	7.251	8	0.451	0.305	7.422	7.275
9	0.395	0.253	7.365	7.224	9	0.429	0.275	7.399	7.245
10	0.358	0.000	7.328	6.970	10	0.388	0.000	7.359	6.970
11	0.322	0.253	7.292	7.223	11	0.349	0.274	7.319	7.244
12	0.243		7.213		12	0.263		7.233	
RPM=580	H=50.10	P=48.07	P (psi) = 6.972	RPM=600	H=50.26	P=48.07	P (psi) = 6.972		
Fri	May	13	14:14:23 1994	Fri	May	13	14:16:26 1994		
Transducer	Average (psid)		Average (psia)	Transducer	Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.000	0.000	6.972	6.971	1	0.000	0.000	6.972	6.971
2	0.030	0.029	7.001	7.001	2	0.030	0.029	7.001	7.001
3	0.205	0.092	7.177	7.063	3	0.221	0.099	7.192	7.070
4	0.198	0.071	7.169	7.043	4	0.212	0.076	7.183	7.048
5	0.192	0.126	7.164	7.098	5	0.206	0.136	7.178	7.108
6	0.189	0.328	7.161	7.299	6	0.202	0.352	7.174	7.324
7	0.185	0.329	7.157	7.300	7	0.199	0.353	7.171	7.325
8	0.485	0.328	7.457	7.300	8	0.522	0.353	7.494	7.325
9	0.463	0.296	7.435	7.268	9	0.498	0.319	7.470	7.291
10	0.420	0.000	7.392	6.972	10	0.451	0.000	7.423	6.972
11	0.377	0.296	7.349	7.267	11	0.404	0.318	7.375	7.290
12	0.284		7.256		12	0.305		7.276	
RPM=620	H=50.41	P=48.06	P (psi) = 6.970	RPM=640	H=50.59	P=48.06	P (psi) = 6.970		
Fri	May	13	14:18:09 1994	Fri	May	13	14:20:26 1994		
Transducer	Average (psid)		Average (psia)	Transducer	Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.000	0.000	6.971	6.970	1	0.000	0.000	6.971	6.970
2	0.030	0.030	7.000	7.000	2	0.030	0.029	7.000	7.000
3	0.236	0.105	7.206	7.076	3	0.252	0.113	7.223	7.083
4	0.228	0.082	7.198	7.052	4	0.244	0.088	7.214	7.058
5	0.222	0.146	7.192	7.116	5	0.237	0.157	7.207	7.127
6	0.217	0.378	7.188	7.348	6	0.233	0.404	7.203	7.375
7	0.213	0.379	7.184	7.349	7	0.229	0.405	7.199	7.375
8	0.562	0.378	7.532	7.349	8	0.602	0.405	7.573	7.375
9	0.535	0.342	7.505	7.313	9	0.572	0.367	7.542	7.337
10	0.486	0.000	7.456	6.970	10	0.518	0.000	7.489	6.970
11	0.433	0.342	7.404	7.312	11	0.463	0.366	7.433	7.337
12	0.326		7.297		12	0.348		7.318	
RPM=660	H=50.76	P=48.08	P (psi) = 6.973	RPM=680	H=50.95	P=48.08	P (psi) = 6.973		
Fri	May	13	14:22:36 1994	Fri	May	13	14:24:44 1994		
Transducer	Average (psid)		Average (psia)	Transducer	Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.000	0.000	6.974	6.973	1	0.000	0.000	6.974	6.973
2	0.030	0.029	7.003	7.003	2	0.030	0.029	7.003	7.003
3	0.270	0.120	7.243	7.093	3	0.286	0.128	7.259	7.101
4	0.260	0.093	7.233	7.066	4	0.276	0.099	7.249	7.072
5	0.253	0.167	7.226	7.140	5	0.269	0.177	7.242	7.150
6	0.249	0.430	7.222	7.404	6	0.264	0.458	7.238	7.431
7	0.244	0.431	7.217	7.405	7	0.259	0.460	7.232	7.433
8	0.643	0.432	7.616	7.405	8	0.684	0.459	7.657	7.433
9	0.611	0.391	7.584	7.365	9	0.649	0.417	7.623	7.390
10	0.553	0.000	7.526	6.973	10	0.589	0.000	7.562	6.973
11	0.493	0.391	7.466	7.364	11	0.526	0.417	7.499	7.390
12	0.370		7.343		12	0.394		7.367	

RPM=700				RPM=720					
Fri	H=51.13	P=48.10	P (psi) = 6.976	Fri	H=51.33	P=48.12	P (psi) = 6.979		
Transducer	May		13 14:27:02	May		13 14:29:10	1994		
	Average (psid)		Average (psia)		Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.001	0.000	6.977	6.976	1	0.000	0.000	6.979	6.979
2	0.029	0.029	7.005	7.006	2	0.030	0.029	7.009	7.008
3	0.305	0.136	7.281	7.112	3	0.323	0.144	7.302	7.123
4	0.293	0.105	7.269	7.082	4	0.311	0.112	7.289	7.091
5	0.286	0.189	7.262	7.165	5	0.303	0.200	7.282	7.179
6	0.281	0.487	7.257	7.463	6	0.298	0.516	7.277	7.495
7	0.276	0.488	7.252	7.464	7	0.292	0.517	7.271	7.496
8	0.728	0.487	7.704	7.463	8	0.773	0.516	7.752	7.495
9	0.692	0.444	7.668	7.420	9	0.733	0.471	7.712	7.450
10	0.628	0.000	7.604	6.976	10	0.665	0.000	7.644	6.979
11	0.559	0.443	7.535	7.419	11	0.592	0.470	7.571	7.449
12	0.416		7.392		12	0.441		7.420	
RPM=740				RPM=760					
Fri	H=51.53	P=48.10	P (psi) = 6.976	Fri	H=51.72	P=48.08	P (psi) = 6.973		
Transducer	May		13 14:31:12	May		13 14:32:56	1994		
	Average (psid)		Average (psia)		Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.001	0.000	6.977	6.976	1	0.001	0.000	6.974	6.973
2	0.030	0.029	7.006	7.005	2	0.030	0.029	7.003	7.003
3	0.343	0.153	7.319	7.130	3	0.365	0.163	7.338	7.136
4	0.329	0.119	7.305	7.096	4	0.350	0.127	7.323	7.100
5	0.320	0.212	7.296	7.188	5	0.340	0.225	7.313	7.198
6	0.315	0.544	7.291	7.520	6	0.334	0.579	7.307	7.552
7	0.309	0.546	7.285	7.522	7	0.328	0.581	7.301	7.554
8	0.816	0.545	7.792	7.521	8	0.869	0.580	7.842	7.553
9	0.775	0.497	7.751	7.473	9	0.826	0.530	7.799	7.503
10	0.703	0.000	7.679	6.976	10	0.747	0.000	7.720	6.973
11	0.625	0.496	7.601	7.472	11	0.664	0.529	7.637	7.502
12	0.466		7.443		12	0.494		7.467	
RPM=780				RPM=800					
Fri	H=51.95	P=48.12	P (psi) = 6.979	Fri	H=52.16	P=48.10	P (psi) = 6.976		
Transducer	May		13 14:35:35	May		13 14:37:25	1994		
	Average (psid)		Average (psia)		Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.001	0.000	6.980	6.979	1	0.001	0.000	6.977	6.976
2	0.030	0.029	7.009	7.008	2	0.030	0.030	7.006	7.006
3	0.383	0.173	7.362	7.152	3	0.404	0.183	7.380	7.159
4	0.369	0.134	7.348	7.113	4	0.388	0.142	7.364	7.118
5	0.359	0.239	7.338	7.218	5	0.378	0.252	7.354	7.228
6	0.352	0.610	7.331	7.589	6	0.371	0.644	7.347	7.620
7	0.345	0.612	7.324	7.591	7	0.365	0.645	7.341	7.621
8	0.912	0.611	7.891	7.590	8	0.961	0.644	7.937	7.620
9	0.867	0.558	7.845	7.537	9	0.914	0.589	7.890	7.565
10	0.785	0.000	7.764	6.979	10	0.828	0.000	7.804	6.976
11	0.698	0.557	7.677	7.536	11	0.735	0.589	7.711	7.565
12	0.519		7.498		12	0.547		7.523	
RPM=820				RPM=840					
Fri	H=52.36	P=48.08	P (psi) = 6.973	Fri	H=52.59	P=48.10	P (psi) = 6.976		
Transducer	May		13 14:39:37	May		13 14:41:46	1994		
	Average (psid)		Average (psia)		Average (psid)		Average (psia)		
	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	sc-01	sc-02	
1	0.001	0.000	6.974	6.973	1	0.001	0.000	6.977	6.976
2	0.030	0.029	7.003	7.002	2	0.030	0.030	7.006	7.006
3	0.425	0.193	7.398	7.166	3	0.447	0.204	7.423	7.180
4	0.408	0.150	7.381	7.123	4	0.431	0.158	7.407	7.134
5	0.397	0.265	7.370	7.239	5	0.420	0.280	7.397	7.256
6	0.388	0.674	7.361	7.647	6	0.412	0.711	7.388	7.687
7	0.382	0.676	7.355	7.650	7	0.404	0.712	7.380	7.689
8	1.011	0.676	7.984	7.649	8	1.063	0.711	8.039	7.687
9	0.960	0.619	7.933	7.592	9	1.013	0.652	7.989	7.628
10	0.870	0.000	7.843	6.974	10	0.917	0.000	7.893	6.976
11	0.773	0.618	7.746	7.591	11	0.812	0.651	7.788	7.627
12	0.575		7.549		12	0.602		7.578	

RPM=860				H=52.81 P=48.09				P (psi) = 6.975				RPM=880				H=53.14 P=48.15				P (psi) = 6.983			
Fri	May	13	14:43:46	Average (psid)		Average (psia)		P (psi) = 6.975				Fri	May	13	14:47:25	Average (psid)		Average (psia)		P (psi) = 6.983			
Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02	
	1	0.001	0.000		6.975	6.975			1	0.001	0.000		6.984	6.984			1	0.001	0.000		6.984	6.984	
	2	0.030	0.030		7.004	7.004			2	0.030	0.029		7.013	7.013			2	0.030	0.029		7.013	7.013	
	3	0.468	0.214		7.443	7.189			3	0.493	0.226		7.476	7.209			3	0.493	0.226		7.476	7.209	
	4	0.451	0.166		7.426	7.141			4	0.474	0.176		7.457	7.159			4	0.474	0.176		7.457	7.159	
	5	0.439	0.295		7.414	7.269			5	0.462	0.311		7.446	7.294			5	0.462	0.311		7.446	7.294	
	6	0.431	0.746		7.406	7.720			6	0.454	0.784		7.437	7.768			6	0.454	0.784		7.437	7.768	
	7	0.422	0.747		7.397	7.722			7	0.444	0.787		7.428	7.770			7	0.444	0.787		7.428	7.770	
	8	1.118	0.746		8.092	7.721			8	1.176	0.786		8.160	7.770			8	1.176	0.786		8.160	7.770	
	9	1.067	0.685		8.042	7.659			9	1.121	0.721		8.104	7.705			9	1.121	0.721		8.104	7.705	
	10	0.965	0.000		7.939	6.975			10	1.013	0.000		7.997	6.984			10	1.013	0.000		7.997	6.984	
	11	0.854	0.684		7.829	7.658			11	0.898	0.720		7.881	7.704			11	0.898	0.720		7.881	7.704	
	12	0.634			7.608				12	0.666			7.650				12	0.666			7.650		
RPM=900	H=53.35	P=48.14		P (psi) = 6.982				RPM=920	H=53.61	P=48.15		P (psi) = 6.983				RPM=920	H=53.61	P=48.15		P (psi) = 6.983			
Fri	May	13	14:48:53	Average (psid)		Average (psia)		Fri	May	13	14:51:16	Average (psid)		Average (psia)		Fri	May	13	14:51:16	Average (psid)		Average (psia)	
Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02	
	1	0.001	0.000		6.983	6.982			1	0.001	0.000		6.984	6.984			1	0.001	0.000		6.984	6.984	
	2	0.030	0.029		7.012	7.011			2	0.030	0.030		7.013	7.013			2	0.030	0.030		7.013	7.013	
	3	0.514	0.234		7.496	7.216			3	0.544	0.247		7.527	7.230			3	0.544	0.247		7.527	7.230	
	4	0.494	0.182		7.476	7.164			4	0.523	0.192		7.506	7.175			4	0.523	0.192		7.506	7.175	
	5	0.482	0.323		7.464	7.304			5	0.510	0.340		7.493	7.323			5	0.510	0.340		7.493	7.323	
	6	0.472	0.818		7.454	7.800			6	0.501	0.864		7.484	7.847			6	0.501	0.864		7.484	7.847	
	7	0.463	0.820		7.445	7.802			7	0.490	0.865		7.473	7.849			7	0.490	0.865		7.473	7.849	
	8	1.228	0.820		8.210	7.801			8	1.302	0.864		8.286	7.847			8	1.302	0.864		8.286	7.847	
	9	1.171	0.753		8.153	7.735			9	1.233	0.795		8.217	7.778			9	1.233	0.795		8.217	7.778	
	10	1.059	0.000		8.040	6.982			10	1.112	0.001		8.095	6.984			10	1.112	0.001		8.095	6.984	
	11	0.938	0.752		7.919	7.734			11	0.984	0.794		7.967	7.777			11	0.984	0.794		7.967	7.777	
	12	0.690			7.672				12	0.723			7.706				12	0.723			7.706		
RPM=940	H=53.89	P=48.18		P (psi) = 6.988				RPM=960	H=54.21	P=48.23		P (psi) = 6.995				RPM=960	H=54.21	P=48.23		P (psi) = 6.995			
Fri	May	13	14:53:31	Average (psid)		Average (psia)		Fri	May	13	14:56:31	Average (psid)		Average (psia)		Fri	May	13	14:56:31	Average (psid)		Average (psia)	
Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02	
	1	0.001	0.001		6.989	6.988			1	0.001	0.001		6.996	6.996			1	0.001	0.001		6.996	6.996	
	2	0.030	0.030		7.017	7.017			2	0.030	0.030		7.024	7.024			2	0.030	0.030		7.024	7.024	
	3	0.564	0.256		7.551	7.244			3	0.590	0.268		7.585	7.263			3	0.590	0.268		7.585	7.263	
	4	0.540	0.201		7.528	7.189			4	0.567	0.210		7.562	7.205			4	0.567	0.210		7.562	7.205	
	5	0.526	0.352		7.513	7.340			5	0.553	0.368		7.548	7.363			5	0.553	0.368		7.548	7.363	
	6	0.515	0.896		7.503	7.884			6	0.542	0.937		7.537	7.931			6	0.542	0.937		7.537	7.931	
	7	0.506	0.899		7.494	7.886			7	0.531	0.939		7.526	7.934			7	0.531	0.939		7.526	7.934	
	8	1.349	0.897		8.337	7.884			8	1.403	0.938		8.398	7.933			8	1.403	0.938		8.398	7.933	
	9	1.287	0.826		8.275	7.813			9	1.347	0.864		8.342	7.859			9	1.347	0.864		8.342	7.859	
	10	1.160	0.001		8.147	6.988			10	1.214	0.001		8.209	6.996			10	1.214	0.001		8.209	6.996	
	11	1.026	0.825		8.013	7.812			11	1.072	0.862		8.067	7.857			11	1.072	0.862		8.067	7.857	
	12	0.754			7.741				12	0.789			7.784				12	0.789			7.784		
RPM=980	H=54.46	P=48.27		P (psi) = 7.001				RPM=1000	H=54.72	P=48.23		P (psi) = 6.995				RPM=1000	H=54.72	P=48.23		P (psi) = 6.995			
Fri	May	13	14:58:20	Average (psid)		Average (psia)		Fri	May	13	15:00:15	Average (psid)		Average (psia)		Fri	May	13	15:00:15	Average (psid)		Average (psia)	
Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02		Transducer		sc-01	sc-02		sc-01	sc-02	
	1	0.001	0.001		7.002	7.001			1	0.001	0.001		6.996	6.996			1	0.001	0.001		6.996	6.996	
	2	0.030	0.029		7.030	7.030			2	0.030	0.029		7.025	7.024			2	0.030	0.029		7.025	7.024	
	3	0.614	0.280		7.615	7.280			3	0.641	0.291		7.636	7.286			3	0.641	0.291		7.636	7.286	
	4	0.592	0.219		7.593	7.220			4	0.616	0.229		7.611	7.224			4	0.616	0.229		7.611	7.224	
	5	0.577	0.386		7.578	7.386			5	0.601	0.401		7.596	7.396			5	0.601	0.401		7.596	7.396	
	6	0.566	0.977		7.567	7.977			6	0.592	1.019		7.587	8.014			6	0.592	1.019		7.587	8.014	
	7	0.556	0.979		7.556	7.980			7	0.581	1.021		7.576	8.016			7	0.581	1.021		7.576	8.016	
	8	1.469	0.978		8.470	7.979			8	1.526	1.020		8.521	8.015			8	1.526	1.020		8.521	8.015	
	9	1.407	0.901		8.408	7.902			9	1.473	0.941		8.468	7.936			9	1.473	0.941		8.468	7.936	
	10	1.269	0.001		8.270	7.001			10	1.328	0.001		8.322	6.996</									

RPM=1020 H=55.02 P=48.30 May 13 15:02:42 1994				RPM=1040 H=55.27 P=48.31 May 13 15:04:37 1994					
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.001	0.001	7.006	7.006	1	0.001	0.001	7.008	7.007
2	0.030	0.030	7.035	7.035	2	0.030	0.030	7.036	7.036
3	0.665	0.303	7.670	7.308	3	0.688	0.314	7.695	7.320
4	0.639	0.237	7.644	7.242	4	0.664	0.245	7.670	7.252
5	0.624	0.416	7.629	7.421	5	0.646	0.431	7.653	7.438
6	0.613	1.060	7.618	8.065	6	0.634	1.094	7.641	8.100
7	0.600	1.063	7.605	8.068	7	0.621	1.097	7.627	8.104
8	1.588	1.061	8.593	8.066	8	1.653	1.095	8.660	8.102
9	1.532	0.980	8.537	7.985	9	1.592	1.012	8.598	8.019
10	1.383	0.001	8.388	7.006	10	1.430	0.001	8.437	7.007
11	1.215	0.978	8.220	7.983	11	1.256	1.010	8.262	8.017
12	0.893		7.898		12	0.925		7.931	
RPM=1060 H=55.54 P=48.28 May 13 15:06:12 1994				RPM=1080 H=55.81 P=48.28 May 13 15:08:01 1994					
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.001	0.001	7.003	7.003	1	0.001	0.001	7.003	7.003
2	0.030	0.030	7.032	7.032	2	0.030	0.029	7.032	7.032
3	0.716	0.326	7.718	7.328	3	0.745	0.341	7.747	7.343
4	0.690	0.255	7.692	7.257	4	0.715	0.270	7.717	7.272
5	0.671	0.448	7.673	7.450	5	0.694	0.467	7.696	7.470
6	0.657	1.137	7.659	8.139	6	0.676	1.182	7.678	8.184
7	0.642	1.140	7.644	8.142	7	0.661	1.186	7.663	8.188
8	1.710	1.138	8.712	8.140	8	1.772	1.184	8.775	8.186
9	1.657	1.053	8.659	8.055	9	1.723	1.096	8.725	8.098
10	1.485	0.001	8.487	7.003	10	1.545	0.001	8.547	7.003
11	1.306	1.051	8.308	8.053	11	1.358	1.094	8.360	8.096
12	0.965		7.967		12	1.003		8.005	
RPM=1100 H=56.13 P=48.34 May 13 15:10:20 1994				RPM=1120 H=56.45 P=48.33 May 13 15:12:18 1994					
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.001	0.001	7.012	7.012	1	0.002	0.001	7.011	7.010
2	0.030	0.030	7.041	7.040	2	0.030	0.030	7.039	7.039
3	0.765	0.353	7.776	7.364	3	0.796	0.368	7.806	7.378
4	0.732	0.278	7.743	7.288	4	0.764	0.288	7.773	7.297
5	0.711	0.483	7.722	7.494	5	0.739	0.504	7.749	7.513
6	0.696	1.221	7.707	8.232	6	0.722	1.270	7.731	8.280
7	0.681	1.225	7.692	8.236	7	0.708	1.274	7.718	8.283
8	1.837	1.223	8.848	8.234	8	1.912	1.271	8.921	8.280
9	1.781	1.132	8.792	8.143	9	1.851	1.178	8.861	8.188
10	1.593	0.001	8.604	7.012	10	1.659	0.001	8.668	7.010
11	1.401	1.131	8.412	8.142	11	1.460	1.177	8.470	8.186
12	1.036		8.047		12	1.077		8.086	
RPM=1140 H=56.78 P=48.35 May 13 15:14:25 1994				RPM=1160 H=57.09 P=48.38 May 13 15:16:14 1994					
Transducer	Average (psid)		Average (psia)		Transducer	Average (psid)		Average (psia)	
	sc-01	sc-02	sc-01	sc-02		sc-01	sc-02	sc-01	sc-02
1	0.002	0.001	7.014	7.013	1	0.002	0.001	7.018	7.018
2	0.030	0.030	7.042	7.042	2	0.030	0.030	7.047	7.046
3	0.823	0.382	7.835	7.394	3	0.850	0.396	7.866	7.413
4	0.787	0.299	7.799	7.312	4	0.811	0.310	7.827	7.326
5	0.761	0.523	7.774	7.535	5	0.787	0.540	7.803	7.557
6	0.745	1.313	7.757	8.326	6	0.768	1.359	7.785	8.376
7	0.733	1.318	7.745	8.330	7	0.754	1.364	7.771	8.380
8	1.976	1.315	8.988	8.328	8	2.038	1.362	9.055	8.379
9	1.913	1.220	8.925	8.232	9	1.984	1.263	9.001	8.280
10	1.719	0.001	8.732	7.013	10	1.784	0.001	8.801	7.018
11	1.511	1.218	8.523	8.231	11	1.565	1.262	8.582	8.278
12	1.108		8.121		12	1.151		8.168	

RPM=0    H=53.51    P=53.51    P (psi) = 7.761  
Fri       May              13 15:20:01      1994  
Average (psid)              Average (psia)  
**Transducer**    sc-01    sc-02    sc-01    sc-02

1	0.001	0.000	7.761	7.760
2	0.025	0.025	7.786	7.785
3	0.001	0.001	7.762	7.761
4	0.000	0.000	7.761	7.761
5	0.000	0.001	7.761	7.761
6	0.001	0.001	7.761	7.761
7	0.000	0.001	7.761	7.762
8	0.001	0.000	7.761	7.761
9	0.000	0.000	7.761	7.761
10	0.001	0.000	7.762	7.761
11	0.001	0.001	7.761	7.761
12	0.001	7.761		

## A.4 Pressure Coefficients - Nozzle Comparison (MAX1, MAX2)

	MAX1			MAX2		
	Nozzle 1	Nozzle 2	Nozzle 3	Nozzle 1	Nozzle 2	Nozzle 3
R1T1	0.694	0.686	0.676	0.691	0.685	0.678
R1T2	0.674	0.667	0.648	0.671	0.666	0.650
R1T3	0.660	0.654	0.628	0.659	0.653	0.629
R1T4	0.648	0.642	0.614	0.647	0.641	0.615
R1T5	0.636	0.629	0.602	0.634	0.628	0.603
R2T1	1.380	1.446	1.626	1.383	1.448	1.625
R2T2	1.382	1.435	1.574	1.383	1.438	1.572
R2T3	1.263	1.302	1.409	1.264	1.303	1.407
R2T4	1.154	1.177	1.239	1.156	1.178	1.237
R2T5	0.929	0.922	0.915	0.928	0.922	0.914
B1	0.446	0.408	0.310	0.442	0.406	0.311
A1	0.398	0.354	0.244	0.394	0.351	0.245
B2	0.524	0.496	0.425	0.521	0.494	0.426
B3	1.054	1.061	1.079	1.055	1.062	1.078
A3	1.058	1.064	1.083	1.058	1.065	1.082
A4	1.055	1.061	1.080	1.056	1.063	1.079
SC	1.001	1.000	1.001	1.001	1.001	1.000
PC	0.001	0.001	0.001	0.001	0.001	0.001
TOT	1.000	1.000	1.000	1.000	1.000	1.000

DSTO-TN-0150

## A.5 Temperature and Flow Rate Data

DSTO-TN-0150

Date: 9/05/1994  
Test: N1 INCR

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	T wet (°F)	T dry (°F)	q (l/s)
[3:51]	0	49.60	49.60	0.000	14.7	15.0	12.1	12.6	11.8	10.8	9.0	10.7	16.9	16.6	16.2	16.5	16.5	16.6	61.0	55.8	
14:10	400	50.38	49.16	0.190	17.1	17.5	16.3	16.9	16.7	16.9	16.1	16.6	17.0	16.8	16.4	16.7	16.7	16.6	58.0	56.6	
14:25	420	51.01	49.65	0.197	18.4	18.7	18.3	18.7	17.2	17.4	16.6	17.1	16.9	17.2	17.3	17.0	16.9	57.0	60.0		
14:30	440	51.23	49.69	0.209	18.5	18.9	18.4	18.9	17.3	17.5	16.7	17.2	17.1	16.9	17.3	17.5	17.1	17.0	58.0	61.0	
14:31	460	51.38	49.72	0.219	18.7	19.1	18.7	19.1	17.4	17.6	16.8	17.3	17.1	16.9	17.5	17.6	17.2	17.0		55.1	
14:34	480	51.53	49.70	0.229	18.9	19.4	18.9	19.3	17.4	17.7	16.9	17.4	17.1	16.9	17.6	17.7	17.2	17.1	57.0	60.0	
14:36	500	51.69	49.69	0.239	19.2	19.6	19.2	19.6	17.6	17.8	17.0	17.5	17.0	17.0	17.7	17.8	17.3	17.1		55.8	
14:38	520	51.83	49.67	0.249	19.5	19.9	19.4	19.8	17.7	17.9	17.1	17.6	17.1	17.0	17.9	18.0	17.4	17.2		56.6	
14:40	540	52.00	49.65	0.259	19.8	20.2	19.8	20.2	17.8	18.1	17.3	17.8	17.1	17.0	18.1	18.1	17.5	17.2		55.6	
14:43	560	52.20	49.63	0.269	20.2	20.7	20.2	20.6	18.0	18.3	17.5	18.0	17.2	17.0	18.3	18.3	17.6	17.4		56.3	
14:47	580	52.37	49.61	0.280	21.0	20.5	20.6	21.0	18.6	18.2	17.7	18.5	17.2	17.0	18.5	18.5	17.8	17.5		56.6	
14:49	600	52.59	49.62	0.290	21.0	21.0	21.0	21.4	18.4	18.8	17.9	18.4	17.2	17.0	18.8	18.7	18.0	17.7		55.8	
14:50	620	52.82	49.65	0.300	21.6	22.1	21.6	21.9	18.8	19.2	18.3	18.8	17.2	17.1	19.2	19.0	18.3	17.9		55.8	
14:54	640	53.07	49.65	0.311	22.1	22.6	22.1	22.5	19.1	19.5	18.6	19.1	17.2	17.1	19.6	19.4	18.5	18.1		55.6	
14:56	660	53.30	49.61	0.322	22.6	23.1	22.6	23.0	19.4	19.8	18.9	19.4	17.3	17.2	19.9	19.6	18.7	18.3		56.3	
15:00	680	53.50	49.61	0.331	23.1	23.7	23.2	23.5	19.7	20.1	19.2	19.7	17.3	17.2	20.2	19.9	19.0	18.4		56.0	59.0
15:02	700	53.71	49.57	0.341	23.6	24.2	23.7	24.0	19.9	20.4	19.4	20.0	17.3	17.2	20.5	20.2	19.1	18.5		55.6	
15:04	720	53.94	49.54	0.352	24.1	24.7	24.3	24.6	20.3	20.7	19.8	20.4	17.4	17.3	20.9	20.5	19.3	18.7		55.5	
15:06	740	54.16	49.51	0.361	24.7	25.3	24.8	25.1	20.5	21.0	20.0	20.6	17.4	17.3	21.3	20.8	19.5	18.8		56.1	
15:08	760	54.40	49.43	0.373	25.3	25.8	25.4	25.7	20.9	21.3	20.3	20.9	17.4	17.4	21.7	21.1	19.7	19.0		56.0	59.0
15:11	780	54.66	49.36	0.384	25.9	26.5	26.0	26.4	21.2	21.7	20.7	20.7	17.3	17.5	22.1	21.5	20.0	19.1		56.1	
15:14	800	54.89	49.35	0.393	26.5	27.1	26.6	27.0	21.6	22.1	21.1	21.7	17.5	17.5	22.5	21.9	20.2	19.3		56.6	
15:17	820	55.26	49.38	0.404	27.5	28.1	27.6	27.9	22.1	22.7	21.6	22.2	17.6	17.6	23.3	22.5	20.6	19.6		56.3	
15:20	840	55.50	49.35	0.414	28.1	28.7	28.3	28.6	22.5	23.0	22.0	22.6	17.7	17.7	23.7	22.5	20.8	19.8		55.5	58.5
15:23	860	55.76	49.30	0.424	28.7	29.4	29.0	29.3	22.9	23.5	22.4	23.0	17.8	17.7	24.2	23.2	21.1	20.0		56.8	
15:25	880	56.06	49.26	0.435	29.7	30.3	29.8	30.1	23.4	24.0	22.9	23.5	17.8	17.7	24.8	23.7	21.4	20.2		55.5	
15:28	900	56.35	49.19	0.445	30.4	31.1	30.6	30.9	23.9	24.4	23.3	24.0	17.9	17.8	25.4	24.1	21.7	20.4		56.3	
15:30	920	56.64	49.15	0.455	31.1	31.8	31.3	31.6	24.3	24.9	23.8	24.4	17.9	17.9	25.8	24.6	22.0	20.5		57.1	
15:32	940	56.90	49.09	0.465	32.0	32.6	32.2	32.5	24.8	25.4	24.3	25.0	18.0	18.0	26.4	25.1	22.3	20.8		56.8	
15:35	960	57.19	49.03	0.474	32.8	33.5	33.0	33.3	25.3	26.0	24.8	25.5	18.1	18.1	27.1	25.6	22.6	21.0		57.8	
15:38	980	57.52	48.98	0.485	33.7	34.4	33.8	34.2	25.8	26.5	25.3	26.0	18.2	18.2	27.6	26.1	23.0	21.2		56.3	
15:40	1000	57.81	48.90	0.495	34.5	35.3	34.8	35.1	26.3	27.1	25.8	26.6	18.3	18.3	28.2	26.5	23.3	21.5		56.0	
15:42	1020	58.12	48.80	0.505	35.4	36.2	35.7	36.0	26.9	27.7	26.4	27.1	18.3	18.3	28.9	27.1	23.8	21.8		57.1	
15:44	1040	58.42	48.79	0.515	36.4	37.2	36.7	37.0	27.5	28.3	27.0	27.8	18.5	18.5	29.6	27.7	24.1	22.0		57.8	
15:46	1060	58.80	48.77	0.525	37.5	38.2	37.8	38.0	28.2	29.0	27.6	28.4	18.6	18.6	30.4	28.4	24.1	21.8		57.1	
15:49	1080	59.07	48.62	0.535	38.2	38.9	38.5	38.7	28.4	29.3	28.0	28.8	18.7	18.7	31.0	29.0	24.7	22.3		57.8	
15:51	1100	59.37	48.48	0.546	39.1	39.8	39.3	39.6	28.7	29.6	28.2	29.1	18.8	18.8	31.6	29.4	24.4	21.9		57.3	
15:54	1120	59.77	48.44	0.555	40.1	40.9	40.4	40.6	29.5	30.3	28.9	29.7	19.0	19.0	32.5	30.3	24.7	22.0		56.8	
15:55	1140	60.13	48.40	0.567	41.1	41.4	41.6	41.6	29.8	30.7	29.3	29.7	19.1	19.1	33.4	31.0	25.0	22.2		57.3	
15:58	1160	60.50	48.33	0.577	42.1	42.9	42.4	42.6	30.6	31.6	30.2	31.0	19.2	19.2	34.0	31.5	25.5	22.3		56.6	
16:04	0	56.05	0.000	35.0	35.3	35.5	35.5	35.6	35.6	24.6	24.6	24.9	24.9	19.3	19.2	33.2	31.4	22.0	21.9	58.0	

Date: 10/05/1994  
 Test: N1 MAXI

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	T <sub>wet</sub> (°F)	T <sub>dry</sub> (°F)	q (°F)
9:40	0	48.40	48.40	0.000	14.2	14.7	12.6	13.0	15.6	14.6	13.5	14.5	17.6	17.4	16.5	16.9	17.3	17.3	17.3	57.3	57.3
9:45	1100	53.30	43.32	0.551	31.0	32.2	31.1	31.5	22.9	23.8	22.5	23.3	17.7	17.5	21.4	20.2	19.7	17.7	55.0	57.0	57.8
9:50	1100	53.82	43.72	0.553	34.1	35.1	34.6	34.7	24.3	25.2	23.9	24.7	17.8	17.7	25.5	24.0	20.7	18.6	57.0	57.1	57.1
9:55	1100	54.50	44.36	0.549	36.2	37.1	36.7	36.7	25.9	26.7	25.5	26.3	18.1	18.0	28.8	27.1	22.1	19.9	53.0	54.5	57.5
10:00	1100	54.89	44.78	0.547	37.3	38.1	37.7	37.9	26.9	27.8	26.4	27.3	18.4	18.3	30.3	28.5	23.1	20.8	57.8	57.8	57.8
10:05	1100	55.22	45.02	0.548	38.2	39.0	38.6	38.7	27.7	28.5	27.2	28.0	18.5	18.5	31.3	29.4	23.8	21.5	55.0	58.0	57.8
10:10	1100	55.60	45.40	0.546	39.0	39.8	39.4	39.6	28.5	29.3	28.0	28.8	18.8	18.8	32.2	30.2	24.5	22.0	57.5	57.5	57.5
10:15	1100	55.85	45.63	0.546	39.5	40.3	39.9	40.0	28.7	29.4	28.0	28.9	19.0	19.0	32.8	30.8	24.4	22.0	55.0	57.5	57.8
10:20	1100	56.08	45.82	0.546	39.6	40.4	40.1	40.2	28.7	29.5	28.2	29.0	19.3	19.3	33.5	31.3	24.5	22.0	57.8	57.8	57.8
10:25	1100	56.33	46.10	0.544	39.8	40.6	40.2	40.4	28.8	29.6	28.3	29.1	19.5	19.6	33.9	31.6	24.5	22.1	54.0	55.0	57.5
10:30	1100	56.61	46.30	0.544	40.1	40.8	40.5	40.6	29.0	29.8	28.4	29.2	19.7	19.8	34.2	32.0	24.6	22.0	57.5	57.5	57.5
10:35	1100	56.92	46.51	0.544	40.4	41.1	40.7	40.9	29.5	30.4	29.0	29.8	20.0	20.1	34.5	32.2	25.1	22.4	55.0	58.0	57.3
10:40	1100	57.10	46.65	0.547	40.4	41.1	40.8	41.0	29.2	30.0	28.6	29.5	20.2	20.3	34.7	32.5	24.7	22.1	57.1	57.1	57.1
10:45	1100	57.34	46.88	0.546	40.6	41.4	41.0	41.2	29.6	30.5	29.0	29.8	20.4	20.5	34.9	32.6	25.1	22.3	55.0	57.0	57.1
10:50	1100	57.52	47.07	0.543	40.6	41.3	40.9	41.1	29.3	30.1	28.8	29.6	20.6	20.7	35.1	32.8	24.8	22.1	57.3	57.3	57.3
10:55	1100	57.75	47.28	0.543	40.7	41.4	41.0	41.2	29.6	30.4	29.0	29.8	20.8	20.9	35.1	32.9	24.9	22.1	55.0	57.0	58.0
11:00	1100	57.94	47.44	0.543	40.7	41.4	41.0	41.2	29.3	30.1	28.7	29.5	21.0	21.1	35.2	33.0	24.7	22.0	57.5	57.5	57.5
11:05	1100	58.18	47.63	0.543	40.8	41.5	41.1	41.3	29.6	30.5	29.2	29.9	21.2	21.3	35.4	33.1	25.2	22.4	55.0	57.5	58.3
11:10	1100	58.41	47.83	0.542	40.9	41.6	41.2	41.4	29.5	30.3	29.0	29.8	21.4	21.5	35.5	33.3	24.9	22.1	57.0	57.0	58.0
11:15	1100	58.71	47.98	0.545	41.2	41.9	41.5	41.7	29.7	30.6	29.2	29.6	21.6	21.7	35.7	33.4	24.9	22.2	55.0	57.0	58.7
11:20	1100	58.88	48.20	0.543	41.1	41.8	41.4	41.7	29.6	30.5	29.1	29.9	21.8	21.9	35.8	33.6	24.9	22.1	57.5	57.5	58.3
11:25	1100	59.14	48.32	0.544	41.2	41.9	41.5	41.7	29.6	30.5	29.1	29.9	22.0	22.1	35.8	33.6	24.9	22.1	55.0	57.0	58.3
11:30	1100	59.33	48.51	0.545	41.3	42.0	41.6	41.9	29.8	30.6	29.2	30.0	22.1	22.3	35.9	33.7	25.0	22.2	58.0	58.0	58.0
11:35	1100	59.56	48.70	0.544	41.5	42.1	41.8	42.0	29.9	30.8	29.4	30.2	22.3	22.4	36.1	33.8	25.1	22.3	55.0	57.0	57.3
11:40	1100	59.76	48.90	0.542	41.5	42.2	41.8	42.0	30.0	30.8	29.4	30.2	22.5	22.6	36.2	33.9	25.2	22.4	57.0	58.3	58.3
11:45	1100	59.97	49.04	0.543	41.5	42.1	41.8	42.0	30.0	30.8	29.4	30.2	22.6	22.7	36.2	34.0	25.2	22.3	55.0	57.5	57.8
11:50	1100	60.27	49.34	0.543	41.5	42.1	41.8	42.0	30.0	30.8	29.4	30.3	22.8	22.9	36.2	34.0	25.2	22.3	58.3	58.3	58.3
11:55	1100	60.57	49.53	0.543	41.6	42.3	42.0	42.2	30.1	31.0	29.5	30.4	22.9	23.0	36.3	34.1	25.3	22.4	54.5	58.0	57.5
12:00	1100	60.89	49.85	0.541	41.7	42.4	42.0	42.2	30.1	31.0	29.6	30.4	23.1	23.2	36.4	34.2	25.2	22.2	58.7	58.7	58.7
12:05	1100	61.12	50.08	0.542	41.6	42.3	41.9	42.2	30.1	30.9	29.5	30.4	23.2	23.3	36.5	34.4	25.1	22.2	55.0	58.0	57.3
12:10	1100	61.46	50.30	0.543	41.8	42.5	42.1	42.4	30.4	31.4	30.0	30.8	23.4	23.5	36.6	34.4	25.4	22.4	58.3	58.3	58.3
12:15	1100	61.76	50.58	0.543	41.7	42.4	42.1	42.3	30.2	31.2	29.8	30.6	23.5	23.6	36.6	34.5	25.6	22.6	55.0	58.0	57.1
12:20	1100	62.00	50.85	0.540	41.7	42.4	42.1	42.3	30.3	31.1	29.7	30.5	23.6	23.7	36.6	34.5	25.1	22.2	58.7	58.7	58.7
12:25	1100	62.29	51.02	0.542	41.8	42.5	42.1	42.4	30.3	31.2	29.7	30.6	23.7	23.8	36.7	34.5	25.3	22.3	55.0	58.0	58.5
12:30	1100	62.59	51.20	0.544	41.8	42.5	42.1	42.4	30.3	31.2	29.7	30.6	23.8	23.9	36.7	34.6	25.4	22.2	58.7	58.7	58.7
12:35	1100	62.85	51.52	0.541	42.0	42.7	42.4	42.5	30.5	31.3	29.9	30.8	23.9	24.1	36.8	34.8	25.2	22.3	55.0	57.0	58.3
12:40	0	58.97	59.00	0.001	36.3	36.7	36.7	36.8	26.1	26.3	25.8	26.1	24.0	23.9	35.9	34.0	22.3	22.3	56.0	57.5	58.7
12:45	0	59.28	59.30	0.001	35.2	35.6	34.1	34.3	26.7	26.7	25.9	26.4	23.9	23.8	35.2	33.6	22.3	22.2	58.3	58.3	58.3
13:45	0	61.13	61.16	0.001	26.8	27.2	24.5	25.0	26.1	25.6	25.0	25.4	23.4	23.4	29.1	28.3	21.9	21.9	58.3	58.3	58.3

Date: 10/05/1994  
 Test: N1 MAX2

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	T wet (°F)	T dry (°F)
18:25	0	48.33	48.33	0.000	16.8	17.3	15.1	15.6	18.7	17.5	16.1	17.4	21.6	21.7	20.8	21.1	18.9	19.0	50.0	53.0
18:30	1107	52.67	42.85	0.553	28.2	29.8	28.0	29.3	23.7	24.8	23.5	24.2	21.5	21.6	23.0	22.2	21.0	19.0	49.5	53.0
18:35	1100	53.12	43.30	0.550	34.7	35.6	34.9	35.2	25.1	26.0	24.7	25.5	21.5	21.6	26.1	24.7	21.6	19.6	49.0	52.5
18:40	1100	53.55	43.62	0.550	36.6	37.4	36.9	37.1	26.2	27.1	25.8	26.6	21.6	21.7	28.9	27.2	22.5	20.3	49.0	53.0
18:45	1100	53.97	44.10	0.546	37.7	38.5	38.1	38.2	27.2	28.1	26.7	27.5	21.7	21.8	30.8	29.0	23.4	21.1	48.5	51.5
18:50	1100	54.31	44.34	0.545	38.6	39.3	38.9	39.1	27.9	28.8	27.4	28.2	21.7	21.8	31.9	29.9	24.0	21.7	49.0	52.0
18:55	1100	54.65	44.66	0.545	39.4	40.1	39.7	39.9	28.5	29.3	27.9	28.8	21.9	21.9	32.9	30.7	24.1	21.8	49.0	52.5
19:00	1100	54.89	44.89	0.546	39.5	40.3	39.9	40.1	28.7	29.6	28.2	29.0	22.0	22.0	33.4	31.3	24.8	22.2	49.0	52.5
19:05	1100	55.18	45.08	0.545	40.0	40.6	40.2	40.4	28.6	29.4	28.0	28.9	22.1	22.1	33.9	31.7	24.4	22.2	49.0	52.5
19:10	1100	55.49	45.36	0.544	40.2	40.9	40.5	40.7	29.1	30.0	28.6	29.4	22.2	22.3	34.2	32.0	24.8	22.1	49.0	52.0
19:15	1100	55.71	45.55	0.545	40.4	41.0	40.6	40.8	28.9	29.7	28.3	29.2	22.3	22.3	34.5	32.2	24.4	21.9	49.0	52.0
19:20	1100	55.95	45.75	0.544	40.3	41.0	40.6	40.8	29.0	29.9	28.6	29.4	22.4	22.5	34.7	32.5	25.1	22.5	49.0	53.0
19:25	1100	56.24	46.02	0.544	40.6	41.2	40.8	41.1	29.4	30.3	28.9	29.6	22.5	22.6	34.9	32.6	24.9	22.1	49.5	53.5
19:30	1100	56.41	46.17	0.543	40.5	41.1	40.7	40.9	29.0	29.8	28.4	29.3	22.6	22.7	35.0	32.7	24.7	22.3	50.0	53.5
19:35	1100	56.66	46.41	0.543	40.5	41.3	40.8	41.0	29.1	30.0	28.6	29.4	22.7	22.8	35.2	33.0	25.1	22.5	50.0	53.5
19:40	1100	56.92	46.60	0.542	40.6	41.2	40.9	41.1	29.1	30.0	28.6	29.4	22.9	22.9	35.4	33.4	24.6	22.1	49.5	53.5
19:45	1100	57.14	46.79	0.542	40.7	41.4	41.0	41.2	29.2	30.0	28.6	29.4	23.0	23.0	35.5	33.6	24.6	22.0	50.0	53.5
19:50	1100	57.38	46.97	0.542	40.8	41.4	41.1	41.3	29.2	30.1	28.7	29.5	23.1	23.1	35.6	33.6	24.6	21.9	50.0	53.5
19:55	1100	57.63	47.22	0.542	40.9	41.6	41.3	41.4	29.5	30.5	29.1	29.9	23.2	23.2	35.6	33.6	25.1	22.3	50.0	53.5
20:00	1100	57.85	47.42	0.541	40.9	41.6	41.3	41.5	29.5	30.4	29.0	29.9	23.3	23.3	35.8	33.7	25.3	22.5	50.0	53.0
20:05	1100	58.14	47.66	0.542	41.1	41.8	41.4	41.7	29.8	30.7	29.3	30.1	23.4	23.4	35.9	34.0	25.0	22.2	50.5	53.5
20:10	1100	58.37	47.75	0.542	41.2	41.8	41.5	41.7	29.6	30.4	29.0	29.9	23.5	23.5	35.9	33.9	24.9	22.3	50.5	53.5
20:15	1100	58.58	47.95	0.543	41.2	41.8	41.5	41.7	29.6	30.4	29.0	29.9	23.6	23.7	36.0	34.0	24.9	22.1	50.5	54.0
20:20	1100	58.81	48.20	0.541	41.2	41.9	41.6	41.7	29.6	30.5	29.0	29.9	23.7	23.8	36.0	34.0	24.9	22.3	50.5	54.0
20:25	1100	59.07	48.43	0.541	41.3	42.0	41.6	41.9	30.0	30.9	29.5	30.2	23.8	23.8	36.1	34.1	25.0	22.2	50.5	53.5
20:30	1100	59.31	48.55	0.541	41.4	42.1	41.7	41.9	29.9	30.7	29.2	30.1	23.9	23.9	36.1	34.2	24.9	22.1	50.0	53.0
20:35	1100	59.50	48.72	0.543	41.4	42.0	41.7	41.8	29.7	30.6	29.2	30.0	24.0	24.0	36.2	34.2	25.1	22.5	50.5	53.5
20:40	1100	59.77	49.00	0.540	41.5	42.2	41.8	42.0	30.0	30.8	29.4	30.3	24.1	24.1	36.2	34.2	25.1	22.2	51.0	54.0
20:45	1100	60.01	49.08	0.543	41.6	42.3	41.9	42.1	30.1	30.8	29.4	30.3	24.2	24.2	36.2	33.9	25.0	22.1	51.0	54.0
20:50	1100	60.22	49.27	0.544	41.7	42.3	42.0	42.2	30.0	30.8	29.4	30.3	24.3	24.3	36.3	34.0	25.1	22.5	52.0	54.0
20:55	1100	60.42	49.50	0.542	41.6	42.2	41.9	42.1	29.9	30.8	29.4	30.2	24.4	24.4	36.3	33.9	25.2	22.5	50.0	53.5
21:00	1100	60.61	49.67	0.541	41.6	42.2	41.9	42.1	30.0	30.8	29.4	30.2	24.4	24.4	36.3	33.9	25.0	22.1	50.5	53.5
21:05	1100	60.85	49.90	0.540	41.5	42.2	41.9	42.1	30.1	31.1	29.7	30.5	24.5	24.5	36.6	34.6	25.6	22.6	51.0	54.0
21:10	1100	61.08	50.02	0.541	41.6	42.3	41.9	42.2	30.1	31.1	29.7	30.5	24.6	24.6	36.7	34.7	25.5	22.5	52.0	54.0
21:15	1100	61.34	50.25	0.540	41.7	42.4	42.1	42.3	30.2	31.1	29.6	30.5	24.7	24.7	36.7	34.8	25.1	22.2	52.0	54.0
21:20	1100	61.51	50.40	0.541	41.5	42.2	41.9	42.1	30.1	30.9	29.5	30.3	24.7	24.7	36.7	34.8	25.0	22.1	52.0	54.0
21:25	1100	61.77	50.59	0.542	41.7	42.5	42.2	42.4	30.2	31.1	29.7	30.5	24.8	24.8	36.8	34.9	25.1	22.1	52.0	55.0
21:30	1100	61.97	50.75	0.542	41.7	42.5	42.1	42.3	30.2	31.0	29.6	30.5	24.9	24.9	36.9	34.9	25.1	22.2	52.0	54.0
21:35	0	58.28	0.000	34.2	35.4	35.1	35.3	26.1	26.2	25.7	26.0	24.9	24.8	35.4	33.8	21.8	21.9			



Date: 12/05/1994  
Test: N2 MAXI

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	Tdry (°F)	Twet (°F)	q (°F)
10:10	0	48.08	48.08	0.000	12.3	12.8	9.2	9.7	11.9	11.0	9.0	10.8	18.0	17.7	16.3	16.0	16.1	16.7	16.0	16.1	54.5
10:20	1100	52.65	43.52	0.532	25.9	27.6	25.7	26.9	20.9	22.0	20.8	21.5	18.0	17.7	19.0	18.4	18.2	16.2	16.2	16.2	57.8
10:25	1100	53.26	44.15	0.526	32.6	33.5	33.0	33.1	22.9	23.7	22.5	23.3	18.1	17.8	23.8	22.6	19.3	17.1	50.0	52.0	57.8
10:30	1100	53.75	44.58	0.526	34.3	35.1	34.8	34.8	24.1	24.9	23.6	24.5	18.2	18.2	26.6	25.4	20.3	18.0	58.0	58.0	58.0
10:35	1100	54.08	44.82	0.524	35.2	36.0	35.6	35.8	24.9	25.7	24.4	25.2	18.3	18.0	28.0	26.6	21.0	18.7	50.0	52.5	57.5
10:40	1100	54.47	45.26	0.522	36.0	36.9	36.5	36.7	25.8	26.6	25.3	26.1	18.4	18.2	29.4	27.9	21.9	19.6	58.0	58.0	58.0
10:45	1100	54.94	45.60	0.522	37.4	38.3	37.8	38.0	26.8	27.6	26.4	27.2	18.6	18.4	30.6	29.0	22.9	20.5	50.0	53.0	57.5
10:50	1100	55.26	45.96	0.520	38.1	38.9	38.6	38.7	27.6	28.5	27.2	28.0	18.8	18.6	31.5	29.6	23.7	21.3	58.3	58.3	58.3
10:55	1100	55.70	46.35	0.519	39.2	40.0	39.6	39.8	28.6	29.4	28.1	28.9	19.0	18.8	32.5	30.6	24.7	22.2	57.5	57.5	57.5
11:00	1100	56.00	46.61	0.519	39.7	40.5	40.1	40.3	28.7	29.5	28.2	29.0	19.3	19.0	33.3	31.4	24.7	22.4	50.5	53.5	57.5
11:05	1100	56.29	46.87	0.519	40.0	40.8	40.4	40.6	29.0	29.8	28.5	29.3	19.5	19.2	33.8	31.8	24.8	22.3	58.3	58.3	58.3
11:10	1100	56.56	47.10	0.519	40.3	41.0	40.6	40.8	29.2	30.0	28.7	29.5	19.7	19.4	34.2	32.2	25.2	22.7	51.0	54.0	57.5
11:15	1100	56.84	47.35	0.518	40.5	41.2	40.8	41.0	29.3	30.1	28.7	29.5	20.0	19.6	34.5	32.5	24.9	22.5	57.8	57.8	57.8
11:20	1100	57.17	47.60	0.519	40.7	41.5	41.3	41.3	29.6	30.4	29.0	29.8	20.2	19.9	34.8	32.8	25.0	22.3	51.0	54.0	57.8
11:25	1100	57.39	47.78	0.520	40.8	41.6	41.3	41.4	29.5	30.3	28.9	29.7	20.4	20.1	35.0	33.1	24.9	22.3	58.3	58.3	58.3
11:30	1100	57.61	48.00	0.518	40.8	41.6	41.3	41.5	29.7	30.6	29.3	30.0	20.6	20.2	35.2	33.2	25.2	22.4	51.0	54.5	58.0
11:35	1100	57.87	48.20	0.518	40.8	41.6	41.3	41.5	29.7	30.6	29.2	30.0	20.8	20.4	35.4	33.4	25.5	22.7	58.0	58.0	58.0
11:40	1100	58.12	48.44	0.518	41.0	41.9	41.5	41.7	29.7	30.5	29.1	29.9	21.1	20.6	35.5	33.5	25.0	22.5	51.0	54.5	57.8
11:45	1100	58.40	48.70	0.517	41.0	41.9	41.5	41.7	30.0	30.9	29.5	30.3	21.3	20.8	35.7	33.5	25.3	22.4	57.3	57.3	57.3
11:50	1100	58.66	48.89	0.517	41.4	42.1	41.7	41.9	30.1	30.9	29.5	30.3	21.4	21.0	35.8	33.8	25.2	22.3	51.5	55.0	57.8
11:55	1100	58.83	49.02	0.517	41.2	42.0	41.6	41.9	29.8	30.7	29.3	30.1	21.6	21.2	35.9	33.9	25.1	22.3	58.0	58.0	58.0
12:00	1100	59.06	49.22	0.516	41.1	41.9	41.6	41.8	29.8	30.7	29.3	30.1	21.8	21.4	36.0	33.8	25.3	22.6	51.5	55.0	57.8
12:05	1100	59.35	49.46	0.517	41.3	42.2	41.8	42.0	29.9	30.7	29.3	30.2	22.1	21.6	36.1	34.0	25.3	22.7	57.5	57.5	57.5
12:10	1100	59.61	49.66	0.517	41.3	42.2	41.8	42.1	30.2	31.2	29.8	30.6	22.2	21.8	36.2	34.1	25.6	22.6	52.0	56.0	58.0
12:15	1100	59.78	49.85	0.516	41.4	42.2	41.9	42.1	30.0	30.9	29.4	30.2	22.4	21.9	36.2	34.1	25.1	22.3	58.0	58.0	58.0
12:20	1100	60.04	50.06	0.516	41.3	42.2	41.9	42.1	30.2	31.1	29.7	30.5	22.6	22.2	36.3	34.2	25.3	22.3	53.0	57.0	57.8
12:25	1100	60.29	50.24	0.517	41.6	42.3	42.0	42.2	30.1	30.9	29.5	30.4	22.7	22.3	36.4	34.2	25.1	22.3	58.3	58.3	58.3
12:30	1100	60.43	50.42	0.517	41.5	42.2	41.9	42.1	30.0	30.9	29.4	30.3	22.8	22.4	36.4	34.2	25.2	22.4	52.0	56.0	58.5
12:35	1100	60.77	50.64	0.517	41.8	42.6	42.2	42.4	30.4	31.3	29.8	30.6	23.0	22.5	36.5	34.3	25.3	22.2	58.0	58.0	58.0
12:40	1100	60.94	50.83	0.517	41.6	42.4	42.0	42.3	30.3	31.2	29.8	30.6	23.1	22.7	36.6	34.5	25.9	22.8	53.0	57.0	58.0
12:45	1100	61.22	51.07	0.516	41.7	42.6	42.2	42.7	30.3	31.2	29.7	30.5	23.3	22.8	36.7	34.4	25.2	22.2	57.1	58.7	58.7
12:50	1100	61.44	51.21	0.515	41.7	42.3	42.0	42.4	30.3	31.1	29.7	30.5	23.4	22.9	36.7	34.5	25.3	22.2	53.0	57.0	58.0
12:55	1100	61.75	51.57	0.515	42.3	43.3	42.9	43.1	31.4	32.5	31.1	31.9	23.6	23.1	36.9	34.6	27.2	22.2	57.0	40.9	43.2
13:00	1100	62.07	51.81	0.515	43.2	44.0	43.6	43.8	31.9	32.7	31.2	32.1	23.7	23.2	37.4	35.1	26.5	22.2	54.0	57.0	57.0
13:05	1100	62.06	51.81	0.514	42.3	43.0	42.7	42.9	30.7	31.6	30.2	31.0	23.8	23.4	37.2	35.2	25.9	22.7	55.8	55.8	55.8
13:10	1100	62.28	51.96	0.516	42.0	42.8	42.4	42.7	30.6	31.6	30.2	31.0	24.0	23.5	37.1	35.2	25.8	22.8	54.0	58.0	57.8
13:15	0	58.68	58.70	0.000	36.0	36.5	36.6	36.6	25.9	26.2	25.7	25.8	23.9	23.4	36.0	34.4	22.3	22.3	57.1	57.1	57.1

Date: 12/05/1994  
Test: N2 MAX2

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	T15	Tdry (°F)	Twet (°F)	q (ls)
18:25	0	47.88	17.88	0.000	16.1	16.6	13.7	14.3	17.2	16.2	14.4	16.0	22.1	22.2	21.3	21.6	18.5	18.6	48.0	50.0	59.0	
18:30	1100	52.32	43.05	0.528	30.3	31.9	30.4	31.4	23.8	24.8	23.5	24.3	21.9	22.1	24.0	23.2	20.6	18.6	48.0	51.0	59.0	
18:35	1100	52.58	43.55	0.526	33.8	34.0	34.3	34.4	24.5	25.3	24.1	24.9	21.9	22.0	24.8	24.9	21.0	18.8	48.0	50.5	59.0	
18:40	1100	52.96	44.00	0.521	35.7	36.7	36.3	36.4	25.6	26.4	25.2	26.0	21.9	22.0	28.6	27.3	21.9	19.7	48.0	51.0	58.5	
18:45	1100	53.34	44.31	0.523	37.0	37.9	37.5	37.5	26.5	27.3	26.0	26.8	22.0	22.1	30.3	28.9	22.7	20.4	48.0	50.5	58.3	
18:50	1100	53.73	44.66	0.521	38.0	38.8	38.4	38.4	27.3	28.1	26.8	27.6	22.0	22.1	31.6	30.1	23.4	21.0	48.0	51.0	58.5	
18:55	1100	54.13	44.99	0.520	38.8	39.6	39.3	39.4	28.1	28.9	27.6	28.4	22.1	22.2	32.5	31.0	24.1	21.8	48.0	51.0	58.7	
19:00	1100	54.45	45.37	0.517	39.6	40.4	40.0	40.1	28.6	29.3	27.9	28.7	22.2	22.3	33.4	31.8	24.1	21.7	47.0	50.0	58.3	
19:05	1100	54.66	45.57	0.517	39.5	40.3	39.9	40.1	28.6	29.5	28.2	29.0	22.3	22.3	33.8	32.2	24.6	21.9	48.0	51.0	59.0	
19:10	1100	54.95	45.77	0.518	39.8	40.6	40.2	40.4	28.6	29.4	28.0	28.9	22.4	22.4	34.1	32.6	24.3	21.9	48.0	51.0	59.0	
19:15	1100	55.21	46.00	0.518	39.9	40.7	40.3	40.5	28.7	29.7	28.4	29.1	22.5	22.5	34.5	32.9	24.9	22.4	48.0	51.0	58.5	
19:20	1100	55.53	46.12	0.521	40.0	40.8	40.5	40.7	28.9	29.8	28.4	29.2	22.6	22.6	34.7	33.1	24.8	22.4	47.0	50.0	58.5	
19:25	1100	55.77	46.44	0.518	40.3	41.1	40.7	40.9	29.2	30.1	28.7	29.5	22.7	22.7	34.9	33.2	24.7	21.9	48.0	51.0	58.7	
19:30	1100	56.00	46.64	0.518	40.5	41.1	40.9	41.1	29.0	29.8	28.5	29.3	22.9	22.9	35.1	33.4	24.5	21.9	48.5	51.0	58.5	
19:35	1100	56.28	46.89	0.518	40.4	41.3	40.9	41.1	29.3	30.2	28.9	29.7	23.0	22.9	35.3	33.5	25.1	22.3	49.0	51.0	58.5	
19:40	1100	56.49	47.11	0.516	40.4	41.4	41.0	41.2	29.4	30.4	29.0	29.8	23.1	22.9	35.3	33.6	25.1	22.2	49.0	51.0	58.3	
19:45	1100	56.72	47.30	0.515	40.6	41.5	41.1	41.3	29.4	30.2	28.8	29.6	23.2	23.0	35.4	33.8	24.6	21.9	49.0	51.0	58.5	
19:50	1100	56.94	47.50	0.516	40.4	41.4	41.0	41.2	29.2	30.1	28.6	29.4	23.3	23.3	35.5	33.8	24.6	22.1	49.0	51.0	58.3	
19:55	1100	57.19	47.70	0.516	40.3	41.5	41.1	41.4	29.5	30.5	29.1	29.9	23.4	23.2	35.6	34.0	25.3	22.4	49.0	51.0	58.0	
20:00	1100	57.47	47.93	0.516	40.6	41.7	41.3	41.6	29.7	30.5	29.1	29.9	23.5	23.5	35.7	34.0	24.8	22.0	49.0	51.0	57.5	
20:05	1100	57.64	48.05	0.516	40.5	41.6	41.2	41.4	29.3	30.2	28.8	29.6	23.6	23.4	35.8	34.1	24.7	21.9	49.0	51.0	57.5	
20:10	1100	57.83	48.32	0.514	40.5	41.5	41.2	41.4	29.5	30.4	29.0	29.8	23.7	23.4	35.8	34.1	25.3	22.5	49.0	51.0	57.5	
20:15	1100	58.14	48.52	0.515	40.5	41.6	41.3	41.5	29.7	30.6	29.3	30.1	23.8	23.5	35.9	34.2	25.3	22.4	49.0	51.0	57.1	
20:20	1100	58.33	48.69	0.516	40.7	41.6	41.2	41.4	29.3	30.2	28.8	29.6	23.6	23.6	35.9	34.2	25.3	22.4	49.0	51.0	57.1	
20:25	1100	58.58	48.77	0.518	40.9	41.8	41.4	41.6	29.5	30.4	29.0	29.8	23.9	23.7	36.0	34.2	25.2	22.4	49.0	51.0	57.5	
20:30	1100	58.88	49.03	0.518	41.3	42.1	41.7	41.9	29.8	30.6	29.2	30.1	24.0	23.8	36.2	34.4	25.3	22.5	49.0	51.0	57.8	
20:35	1100	59.08	49.24	0.517	41.0	41.8	41.7	41.7	29.8	30.7	29.4	30.1	24.1	23.9	36.2	34.5	25.3	22.4	49.0	51.0	58.5	
20:40	1100	59.32	49.46	0.515	41.2	42.0	41.6	41.8	30.0	31.0	29.6	30.4	24.2	23.9	36.2	34.6	25.3	22.3	49.0	51.0	58.3	
20:45	1100	59.54	49.66	0.516	41.4	42.0	41.7	41.9	29.8	30.7	29.2	30.1	24.3	24.0	36.3	34.6	24.8	22.1	49.0	51.0	58.3	
20:50	1100	59.73	49.86	0.514	41.4	42.1	41.7	41.9	29.8	30.7	29.2	30.1	24.3	24.0	36.5	34.7	24.4	22.1	47.0	50.0	58.7	
20:55	1100	59.98	50.04	0.516	41.5	42.2	41.8	42.0	30.0	30.9	29.4	30.3	24.4	24.1	36.3	34.6	24.8	22.1	49.0	51.0	59.0	
21:00	1100	60.12	50.16	0.515	41.3	42.0	41.6	41.8	29.7	30.7	29.2	30.1	24.5	24.2	36.3	34.7	24.9	22.1	49.0	51.0	59.0	
21:05	1100	60.47	50.40	0.516	41.5	42.3	41.9	42.1	30.2	31.2	29.7	30.5	24.6	24.3	36.4	34.7	25.1	22.1	47.0	50.0	58.7	
21:10	1100	60.65	50.58	0.517	41.7	42.3	42.0	42.2	30.1	31.0	29.5	30.3	24.6	24.4	36.5	34.7	24.8	21.9	49.0	51.0	58.7	
21:15	1100	60.79	50.74	0.515	41.3	42.0	41.6	41.8	29.9	30.9	29.4	30.3	24.7	24.4	36.4	34.8	25.3	22.5	47.0	50.0	57.8	
21:20	1100	61.10	50.96	0.514	41.7	42.3	41.9	42.2	30.2	31.0	29.6	30.4	24.8	24.5	36.5	34.9	24.9	21.9	48.0	51.0	59.0	
21:25	1100	61.30	51.15	0.515	41.7	42.4	42.0	42.2	30.1	31.0	29.5	30.3	24.8	24.5	36.5	34.8	24.8	21.9	47.0	50.0	58.7	
21:30	1096	61.45	51.30	0.515	41.5	42.2	41.8	42.0	29.9	30.8	29.4	30.2	24.9	24.6	36.5	34.7	24.8	21.9	47.0	50.0	58.5	
21:35	0	57.75	57.78	0.000	32.2	32.4	32.5	32.8	24.5	24.6	24.0	24.2	19.7	19.7	34.5	33.2	22.2	21.7	47.0	50.0	58.7	
21:40	0	58.03	58.05	0.000	31.8	32.1	30.9	31.2	25.6	25.6	24.8	24.8	24.5	24.5	33.8	32.3	21.7	21.7	47.0	50.0	58.7	

Date: 13/05/1994  
Test: N3 INCR

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	Twet (°F)	Tdry (°F)	q (l/s)
13:59	0	48.12	48.12	0.000	15.9	16.4	13.7	14.4	14.5	13.8	12.2	13.8	19.2	17.9	18.2	17.4	17.4	17.4	17.4	17.4	58.3
14:00	400	48.73	47.82	0.164	17.4	18.1	16.7	17.4	17.4	17.6	16.8	17.0	17.5	19.1	19.1	18.0	18.3	17.4	17.3	53.0	63.0
14:01	420	48.88	47.87	0.173	18.2	17.9	18.4	17.6	17.6	17.8	17.0	17.5	19.1	19.1	18.1	18.3	17.4	17.3	17.3	58.3	
14:02	440	48.88	48.04	0.181	18.6	19.1	18.4	18.9	18.9	17.6	17.8	17.1	17.5	19.1	19.1	18.2	18.4	17.4	17.3	62.5	
14:04	460	49.14	47.92	0.190	18.9	19.4	19.8	19.3	17.7	17.9	17.1	17.6	19.1	19.1	18.3	18.5	17.5	17.3	17.3	58.0	
14:07	480	49.31	47.96	0.200	19.2	19.7	19.3	19.7	19.7	18.0	17.2	17.7	19.1	19.1	18.5	18.7	17.5	17.3	17.3	58.6	
14:10	500	49.48	48.00	0.209	19.5	20.0	19.6	20.0	20.0	17.8	18.0	17.3	17.8	19.1	19.1	18.7	18.8	17.5	17.3	58.7	
14:13	520	49.65	48.04	0.217	19.7	20.3	19.8	20.2	20.2	17.9	18.1	17.4	17.8	19.1	19.1	18.8	18.9	17.5	17.3	62.0	
14:15	540	49.81	48.06	0.226	20.0	20.5	20.1	20.5	20.5	18.0	18.2	17.4	17.9	19.1	19.1	18.9	19.0	17.5	17.3	58.0	
14:17	560	49.94	48.06	0.236	20.2	20.8	20.3	20.7	20.7	18.0	18.3	17.5	18.0	19.1	19.1	19.1	19.1	17.5	17.3	58.3	
14:19	580	50.10	48.08	0.244	20.5	21.1	20.7	21.0	21.0	18.1	18.4	17.6	18.1	19.1	19.1	19.2	19.3	17.6	17.3	58.4	
14:21	600	50.25	48.06	0.253	20.8	21.4	21.0	21.3	21.3	18.2	18.5	17.7	18.2	19.1	19.1	19.4	19.4	17.7	17.3	58.3	
14:23	620	50.41	48.07	0.263	21.1	21.7	21.3	21.7	21.7	18.4	18.7	18.0	18.5	19.1	19.1	19.5	19.5	17.8	17.3	58.5	
14:25	640	50.55	48.04	0.272	21.5	22.1	21.6	22.0	22.1	18.5	18.8	18.0	18.5	19.1	19.1	19.7	19.7	17.8	17.3	57.8	
14:27	660	50.75	48.07	0.281	21.9	22.5	22.1	22.4	22.4	18.7	19.0	18.2	18.7	19.1	19.1	19.9	19.9	17.9	17.4	58.3	
14:29	680	50.94	48.07	0.288	22.4	23.0	22.5	22.9	22.9	18.9	19.3	18.4	18.9	19.1	19.1	19.1	19.1	17.6	17.3	58.4	
14:32	700	51.13	48.08	0.296	22.8	23.5	23.0	23.4	23.4	19.1	19.5	18.6	19.2	19.1	19.1	19.4	19.4	17.7	17.3	61.0	
14:34	720	51.33	48.09	0.307	23.3	23.9	23.5	23.8	23.8	19.3	19.7	18.8	19.4	19.1	19.1	19.5	19.5	17.8	17.3	58.5	
14:36	740	51.50	48.08	0.316	23.7	24.4	23.9	24.2	24.2	19.5	19.9	19.0	19.6	19.1	19.1	19.7	19.7	17.8	17.3	61.0	
14:37	760	51.68	48.06	0.323	24.2	24.8	24.4	24.8	24.8	19.8	20.2	19.3	19.9	19.1	19.1	20.0	20.1	18.1	17.5	57.8	
14:40	780	51.91	48.10	0.333	24.8	25.5	25.0	25.4	25.4	20.1	20.5	19.6	20.2	19.1	19.1	20.5	20.3	18.2	17.6	58.5	
14:42	800	52.15	48.08	0.342	25.4	26.1	25.7	26.0	26.0	20.4	20.9	19.9	20.5	19.1	19.1	20.8	20.6	18.3	17.6	61.0	
14:44	820	52.36	48.10	0.351	26.0	26.7	26.2	26.5	26.5	20.6	21.2	20.1	20.8	19.1	19.1	21.0	20.7	18.4	17.7	58.5	
14:46	840	52.60	48.08	0.360	26.6	27.3	26.8	27.2	27.2	21.0	21.5	20.5	21.1	19.1	19.1	21.3	21.0	18.6	17.8	59.2	
14:49	860	52.81	48.10	0.367	27.2	27.9	27.5	27.8	27.8	21.3	21.9	20.8	21.5	19.2	19.2	23.3	22.8	19.5	18.3	58.7	
14:51	880	53.11	48.12	0.377	28.1	28.9	28.4	28.7	28.7	21.8	22.4	21.3	21.9	19.2	19.2	21.7	21.3	18.8	17.9	58.5	
14:54	900	53.32	48.14	0.387	28.6	29.4	29.0	29.3	29.3	22.2	22.8	21.7	22.3	19.2	19.2	22.1	21.7	18.9	18.0	58.5	
14:56	920	53.60	48.13	0.394	29.5	30.2	29.8	30.1	30.1	22.6	23.3	22.1	22.8	19.3	19.3	22.5	22.0	19.1	18.7	58.5	
14:58	940	53.86	48.17	0.403	30.4	31.2	30.7	31.0	31.0	23.1	23.8	22.6	23.3	19.3	19.3	22.9	22.3	19.3	18.2	58.7	
15:00	960	54.13	48.20	0.411	31.1	31.9	31.4	31.7	31.7	23.5	24.3	23.0	23.8	19.4	19.4	25.9	24.9	20.6	19.0	58.6	
15:02	980	54.41	48.21	0.418	32.0	32.8	32.3	32.6	32.6	24.1	24.8	23.5	24.1	19.4	19.4	26.5	25.4	21.2	19.4	58.5	
15:05	1000	54.71	48.22	0.429	32.9	33.7	33.2	33.5	33.5	24.6	25.4	24.1	24.9	19.5	19.5	27.1	25.9	21.6	19.7	58.7	
15:07	1020	54.98	48.27	0.437	33.8	34.6	34.1	34.4	34.4	25.1	26.0	24.6	25.4	19.5	19.5	27.8	26.4	21.9	19.9	58.4	
15:09	1040	55.24	48.27	0.444	34.6	35.4	34.9	35.2	35.6	25.6	26.5	25.1	25.9	19.6	19.7	28.3	26.9	22.2	20.1	58.1	
15:11	1060	55.51	48.28	0.452	35.5	36.4	35.8	36.1	36.1	26.2	27.1	25.7	26.5	19.7	19.7	28.9	27.5	22.5	20.3	58.9	
15:13	1080	55.81	48.26	0.462	36.5	37.4	36.9	37.2	37.2	26.8	27.8	26.3	27.1	19.8	19.8	29.6	28.0	22.9	20.6	57.8	
15:15	1100	56.12	48.32	0.468	37.5	38.4	37.9	38.1	38.1	27.4	28.4	26.9	27.8	19.9	19.9	30.3	28.8	23.4	20.8	58.5	
15:18	1120	56.45	48.33	0.476	38.6	39.4	38.9	39.2	39.2	28.0	29.2	27.6	28.5	20.0	20.1	31.1	29.3	23.8	21.1	59.0	
15:20	1140	56.77	48.36	0.484	39.7	40.6	40.0	40.3	40.3	28.7	29.8	28.2	29.1	20.1	20.3	31.8	29.9	24.2	21.4	58.4	
15:22	1160	57.08	48.36	0.492	40.6	41.5	41.0	41.2	41.2	29.3	30.5	28.8	29.7	20.2	20.3	32.4	30.4	24.5	21.6	58.7	
15:29	0	53.76	0.000	32.9	33.2	32.4	32.5	32.5	24.7	24.7	23.6	24.4	20.2	20.2	31.2	31.2	29.8	21.7	52.0	61.5	

Date: 17/05/1994  
 Test: N3 MAXI

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	T <sub>wet</sub> (°F)	Tdry (°F)	q (lb/s)
10:05	0	47.42	0.000	12.2	13.6	11.4	11.8	14.1	12.9	11.4	12.8	18.5	18.1	17.2	17.6	15.7	15.8	49.5	55.0	58.3	
10:15	1100	51.44	44.02	0.473	28.4	20.1	28.7	29.4	21.3	22.3	21.0	21.7	18.3	18.0	20.5	19.7	18.1	15.9	49.5	55.0	57.8
10:20	1100	52.03	44.64	0.471	33.1	34.2	33.8	33.9	23.1	24.0	22.6	23.5	18.4	18.1	25.2	24.0	19.4	17.1	49.5	55.5	57.8
10:25	1100	52.43	45.05	0.470	34.2	35.3	34.9	35.0	24.0	24.9	23.5	24.3	18.5	18.3	27.2	25.9	20.2	17.9	49.5	55.5	58.0
10:30	1100	52.84	45.41	0.469	35.3	36.4	35.9	36.1	24.9	25.9	24.5	25.3	18.7	18.4	28.6	27.2	21.1	18.7	50.0	56.0	57.3
10:35	1100	53.21	47.76	0.469	36.3	37.2	36.8	37.0	25.7	26.7	25.3	26.1	18.8	18.6	29.7	28.2	21.9	19.4	50.0	56.0	58.0
10:40	1100	53.53	46.04	0.468	37.0	38.0	37.6	37.7	26.4	27.4	25.9	26.8	19.0	18.8	30.6	29.0	22.5	20.0	50.0	56.0	58.0
10:45	1102	53.90	46.40	0.470	37.8	38.7	38.3	38.4	27.1	28.1	26.6	27.4	19.2	19.0	31.4	29.7	23.2	20.7	50.0	56.0	57.8
10:50	1100	54.24	46.66	0.468	38.5	39.4	39.0	39.2	27.8	28.8	27.3	28.1	19.5	19.3	32.1	30.3	23.8	21.3	50.0	56.0	57.8
10:55	1100	54.60	47.03	0.467	39.3	40.2	39.8	40.0	28.6	29.6	28.1	28.9	19.7	19.6	32.8	31.0	24.6	22.1	50.0	55.5	57.5
11:00	1100	54.85	47.26	0.465	39.6	40.5	40.1	40.2	28.6	29.6	28.0	28.9	19.9	19.8	33.3	31.5	24.5	22.0	50.0	56.0	57.3
11:05	1100	55.10	47.48	0.467	39.7	40.5	40.2	40.3	28.8	29.7	28.2	29.1	20.1	20.0	33.7	31.9	24.8	22.3	50.0	56.0	58.5
11:10	1100	55.41	47.74	0.465	40.0	40.9	40.5	40.7	29.2	30.2	28.7	29.5	20.4	20.3	34.1	32.3	25.1	22.3	50.0	56.0	58.7
11:15	1100	55.60	47.92	0.465	39.9	40.7	40.4	40.5	28.7	29.8	28.2	29.1	20.6	20.5	34.2	32.4	24.7	22.2	50.0	56.5	58.3
11:20	1100	55.87	48.18	0.465	40.1	41.0	40.6	40.8	29.0	30.0	28.5	29.3	20.8	20.7	34.5	32.7	24.8	21.9	50.0	55.5	57.5
11:25	1100	56.09	48.37	0.465	40.1	40.9	40.6	40.7	29.0	30.0	28.4	29.3	21.0	20.9	34.6	32.8	24.9	22.3	51.0	57.0	58.3
11:30	1100	56.35	48.60	0.465	40.3	41.1	40.8	40.9	29.1	30.1	28.5	29.4	21.2	21.2	34.8	32.9	24.8	21.8	50.0	56.0	58.5
11:35	1100	56.73	48.93	0.465	41.1	42.1	41.7	41.8	30.3	31.4	29.8	30.7	21.4	21.4	35.2	33.3	26.3	21.9	50.0	56.5	58.3
11:40	1100	56.87	49.07	0.465	40.7	41.6	41.3	41.5	29.5	30.4	28.9	29.8	21.6	21.6	35.3	33.5	24.9	22.2	50.0	56.5	57.8
11:45	1100	57.12	49.22	0.465	40.6	41.6	41.2	41.4	29.4	30.4	28.8	29.7	21.8	21.8	35.2	33.3	24.9	22.1	50.0	56.0	58.3
11:50	1100	57.32	49.43	0.465	40.5	41.5	41.1	41.3	29.4	30.4	28.8	29.7	22.0	21.9	35.3	33.3	24.9	22.1	50.0	56.0	58.7
11:55	1100	57.59	49.63	0.467	40.6	41.7	41.3	41.5	29.7	30.7	29.1	30.0	22.1	22.1	35.3	33.5	25.0	22.1	52.0	59.0	58.0
12:00	1100	57.75	49.81	0.464	40.6	41.6	41.3	41.4	29.5	30.5	28.9	29.8	22.3	22.2	35.5	33.6	24.8	22.0	52.0	59.0	58.3
12:05	1100	57.96	50.02	0.464	40.6	41.5	41.2	41.3	29.4	30.4	28.8	29.7	22.4	22.4	35.5	33.6	24.9	22.2	52.0	58.0	58.3
12:10	1100	58.22	50.22	0.465	40.6	41.6	41.2	41.4	29.4	30.4	28.8	29.7	22.5	22.5	35.6	33.7	24.9	22.0	52.0	58.5	57.8
12:15	1100	58.46	50.45	0.463	40.9	41.9	41.6	41.7	29.9	30.9	29.3	30.2	22.7	22.7	35.7	33.7	25.1	22.1	52.0	59.0	58.7
12:20	1100	58.70	50.61	0.464	40.8	41.9	41.5	41.7	29.9	31.0	29.4	30.2	22.9	22.9	35.8	33.9	25.5	22.6	52.0	59.0	58.3
12:25	1100	58.92	50.75	0.467	40.8	41.9	41.5	41.7	29.8	30.9	29.3	30.1	23.0	23.0	35.8	34.0	25.3	22.5	53.0	60.0	58.3
12:30	1100	59.11	51.00	0.464	41.0	42.0	41.6	41.8	29.9	30.9	29.2	30.1	23.1	23.1	35.9	34.2	25.0	22.0	52.0	60.0	58.3
12:35	1100	59.32	51.11	0.465	40.8	41.9	41.6	41.7	29.8	30.8	29.2	30.1	23.2	23.2	35.9	34.2	24.9	21.9	54.0	61.0	58.3
12:39	1100	59.50	51.35	0.463	40.7	41.9	41.5	41.7	30.1	31.1	29.5	30.4	23.3	23.3	35.9	34.2	25.4	22.3	54.0	61.0	57.3
12:45	0	56.48	56.51	0.001	34.2	35.1	34.9	35.0	25.7	26.0	25.2	25.6	23.3	23.2	34.7	33.0	22.1	21.8	55.0	62.0	57.1
12:50	0	56.60	56.62	0.001	33.0	34.0	32.3	32.4	26.2	26.3	25.0	26.0	23.3	23.1	34.1	32.5	21.8	21.7			

Date: 16/05/1994  
Test: N3 MAX2

Time	RPM	H (kPa)	P (kPa)	M	T1	T2	T3	T4	T5	T6	T7	T8	T9	T10	T11	T12	T13	T14	Twet (°F)	Tdry (°F)	q (l/s)
18:35	0	47.67	47.67	0.000	14.0	15.1	12.5	13.0	14.0	13.2	11.5	13.1	18.2	17.9	16.9	13.3	18.4	18.3	54.5	60.0	57.5
18:40	1101	51.59	44.26	0.473	25.7	28.0	26.4	27.8	22.8	23.9	22.6	23.3	18.2	18.0	19.9	19.3	20.4	18.3	55.0	60.0	57.5
18:45	1101	52.38	44.97	0.471	34.5	35.8	35.4	35.5	25.0	26.0	24.6	25.4	18.4	18.2	25.6	24.1	21.6	19.3	55.0	60.0	58.0
18:50	1100	52.81	45.39	0.471	36.0	37.3	36.8	36.9	26.1	27.0	25.6	26.4	18.6	18.4	28.0	26.5	22.5	20.2	58.7	58.7	58.7
18:55	1099	53.23	45.78	0.469	37.0	38.2	37.9	38.0	27.0	28.0	26.6	27.4	18.8	18.7	29.6	28.0	23.4	21.0	57.8	57.8	57.8
19:00	1099	53.61	46.16	0.467	38.3	39.2	38.8	38.9	27.9	28.0	27.4	28.2	19.0	18.9	30.9	29.2	24.1	21.8	55.0	60.0	57.8
19:05	1098	53.99	46.50	0.467	39.1	40.1	39.7	39.8	28.6	29.5	28.0	28.8	19.3	19.2	31.9	30.1	24.4	21.9	58.3	58.3	58.3
19:10	1100	54.24	46.74	0.467	39.3	40.2	39.9	40.0	28.6	29.5	28.0	28.9	19.5	19.5	32.6	30.7	24.7	22.4	54.5	59.5	59.5
19:15	1100	54.56	47.00	0.467	39.7	40.7	40.3	40.5	29.1	30.1	28.6	29.4	19.7	19.7	33.1	31.2	24.9	22.3	58.3	58.3	58.3
19:20	1099	54.81	47.26	0.466	39.9	40.8	40.5	40.6	28.9	29.9	28.3	29.2	20.0	20.0	33.6	31.7	24.9	22.5	55.0	59.5	58.5
19:25	1098	55.05	47.45	0.465	40.0	40.9	40.5	40.7	28.9	29.9	28.4	29.2	20.2	20.2	33.8	31.9	24.6	22.0	57.8	57.8	57.8
19:30	1098	55.31	47.68	0.466	40.2	41.0	40.7	40.8	29.0	30.0	28.4	29.3	20.4	20.4	34.1	32.1	24.6	22.0	55.0	60.0	58.7
19:35	1098	55.58	47.93	0.465	40.2	41.0	40.6	40.8	29.2	30.6	28.7	29.5	20.6	20.6	34.3	32.3	25.1	22.4	57.5	57.5	57.5
19:40	1099	55.85	48.17	0.465	40.5	41.3	40.9	41.1	29.5	30.4	28.9	29.7	20.8	20.9	34.4	32.5	25.0	22.2	54.5	59.5	57.3
19:45	1097	56.04	48.33	0.464	40.3	41.2	40.8	41.0	29.1	30.1	28.5	29.4	21.0	21.1	34.6	32.7	24.7	22.1	57.3	57.3	57.3
19:50	1100	56.28	48.56	0.464	40.4	41.3	40.9	41.1	29.2	30.2	28.6	29.5	21.2	21.2	34.8	32.9	24.7	21.9	58.3	58.3	58.3
19:55	1096	56.54	48.77	0.464	40.6	41.4	41.1	41.2	29.3	30.3	28.7	29.6	21.3	21.4	34.9	33.0	24.8	22.0	55.0	59.5	57.3
20:00	1099	56.77	48.94	0.465	40.5	41.4	41.1	41.2	29.3	30.3	28.7	29.5	21.5	21.5	35.0	33.2	24.7	21.8	54.0	59.0	57.5
20:05	1098	57.05	49.18	0.465	40.6	41.6	41.2	41.4	29.7	30.7	29.1	29.9	21.7	21.8	35.1	33.2	25.1	22.2	57.8	57.8	57.8
20:10	1097	57.25	49.38	0.465	40.6	41.5	41.2	41.4	29.6	30.7	29.1	29.9	21.9	22.0	35.2	33.3	25.4	22.5	53.5	59.0	57.8
20:15	1098	57.48	49.53	0.466	40.7	41.6	41.3	41.5	29.5	30.5	28.9	29.8	22.0	22.1	35.2	33.4	24.8	22.0	55.0	59.5	57.3
20:20	1096	57.68	49.75	0.464	40.1	41.5	41.2	41.4	29.5	30.6	29.0	29.9	22.2	22.3	35.3	33.4	25.2	22.5	53.0	59.0	58.7
20:25	1095	57.89	49.95	0.466	40.2	41.6	41.3	41.5	29.5	30.5	28.9	29.8	22.3	22.4	35.4	33.4	24.8	22.0	54.0	59.0	58.5
20:30	1100	58.16	50.16	0.465	40.3	41.8	41.4	41.6	29.5	30.5	28.9	29.8	22.5	22.6	35.4	33.6	24.7	22.0	52.5	58.5	57.3
20:35	1100	58.43	50.38	0.465	40.9	42.1	41.7	41.9	30.1	31.2	29.5	30.4	22.6	22.7	35.6	33.7	25.4	22.4	57.5	57.5	57.5
20:40	1102	58.66	50.59	0.466	40.5	42.0	41.6	41.8	29.8	30.8	29.2	30.0	22.8	22.8	35.7	33.9	24.9	21.9	52.5	58.0	57.5
20:45	1102	58.83	50.74	0.464	40.4	41.8	41.5	41.7	29.6	30.7	29.0	29.9	22.9	23.0	35.6	33.9	24.8	22.0	57.8	57.8	57.8
20:50	1096	59.05	50.96	0.464	40.5	41.9	41.6	41.7	29.7	30.8	29.2	30.0	23.0	23.1	35.7	34.0	24.9	22.0	52.0	58.0	57.5
20:55	1095	59.30	51.22	0.463	40.4	42.1	41.7	41.9	30.1	31.1	29.5	30.3	23.1	23.2	35.8	34.0	25.1	22.1	57.5	57.5	57.5
21:00	1099	59.54	51.40	0.462	39.9	42.1	41.8	42.0	30.0	31.1	29.4	30.3	23.2	23.3	35.9	34.1	25.1	22.2	52.0	58.5	57.8
21:05	1095	51.58	51.58	0.463	40.0	42.2	41.9	42.0	30.0	31.1	29.6	30.3	23.4	23.4	36.0	34.2	25.1	22.1	57.3	57.3	57.3
21:10	1098	51.79	51.79	0.463	40.2	42.3	41.9	42.1	30.2	31.2	29.6	30.5	23.5	23.6	36.1	34.3	25.3	22.3	52.0	58.0	57.3
21:15	0	56.96	56.99	0.000	32.9	35.5	35.3	35.1	26.1	26.3	25.4	25.9	23.4	23.4	34.9	33.5	22.3	22.3	57.5	57.5	57.5



## A.6 Sound Level Data

Test Date: 9 May 1994

Test: N1 INCR

- Notes:
1. All sound data is measured in dBA.
  2. RPM = 580: Machinery running nearby, when it ceased readings were Peak 66, Slow 53.
  3. RPM = 940: Cars leaving the site.

RPM	Location on AMRL Site							
	1		2		3		4	
	Peak	Slow	Peak	Slow	Peak	Slow	Peak	Slow
0	72	54	72	59	72	60	72	60
400	79	52	73	60	70	59	71	55
420	76	53						
440			72	52				
460					72	61		
480							65	55
500	68	57						
520			73	62				
540					81	68		
560							77	65
580	85	75						
600			75	61				
620					74	60		
640							66	55
660	71	60						
680			72	60				
700					72	60		
720							69	55
740	75	57						
760			73	60				
780					72	62		
840	75	58					70	57
860			68	55				
900					70	58		
920							70	57
940	80	65						
960			67	54				
980					71	59		
1000							74	58
1020	79	64						
1040			75	63				
1080					71	59		
1100							74	62
1120	79	66						
1140			68	55				
1160					72	62		
0	70	57	67	55	70	57	74	57

Test Date: 10 May 1994

Test: N1 MAX1 (Day test)

Notes: 1. All sound data is measured in dBA.

2. Outside building 13: Peak 98, Slow 86; inside control room: Peak 101,  
Slow 90.

RPM	Location on AMRL Site							
	1		2		3		4	
	Peak	Slow	Peak	Slow	Peak	Slow	Peak	Slow
0	72	64	74	55	74	58	69	55
1100	78	58	67	55	80	65	80	62
1100	73	61	72	60	71	59	71	57
1100	72	64	68	55	70	57	70	58
1100	71	59	68	56	69	56	72	56

Test Date: 10 May 1994

Test: N1 MAX2 (Night test)

Notes: 1. All sound data is measured in dBA.

RPM	Location on AMRL Site							
	1		2		3		4	
	Peak	Slow	Peak	Slow	Peak	Slow	Peak	Slow
0	65	55	72	62	67	52	65	53
1100	72	61	73	62	72	61	73	59
1100	72	61	74	62	75	57	76	59
1100	72	58	73	61	69	58	70	55
1100	71	55	72	60	70	58	69	58
1100	68	54	72	61	69	56	71	58
1100	71	57	72	61	70	58	69	55
1100	68	55	72	59	68	55	71	56
1100	70	57	72	61	68	56	71	58
1100	69	56	68	55	67	54	69	56
1100	71	58	68	56	67	54	68	57
1100	70	58	68	55	73	58	71	59
0	64	50	69	55	68	54	68	53

## DISTRIBUTION LIST

Performance Tests of the Original Transonic Wind Tunnel Compressor and Circuit

Yoel Link and Howard Quick

### AUSTRALIA

#### DEFENCE ORGANISATION

##### S&T Program

Chief Defence Scientist  
FAS Science Policy                          } shared copy  
AS Science Corporate Management  
Director General Science Policy Development  
Counsellor Defence Science, London (Doc Data Sheet)  
Counsellor Defence Science, Washington (Doc Data Sheet)  
Scientific Adviser to MRDC Thailand (Doc Data Sheet)  
Director General Scientific Advisers and Trials/Scientific Adviser Policy and  
Command (shared copy)  
Navy Scientific Adviser (Doc Data Sheet and distribution list only)  
Scientific Adviser - Army (Doc Data Sheet and distribution list only)  
Air Force Scientific Adviser  
Director Trials

##### Aeronautical and Maritime Research Laboratory

Director

Chief of Air Operations Division

N. Pollock  
N. Matheson (3 copies)  
Y.Y. Link (2 copies)      H.A. Quick (2 copies)  
P. Malone                   A. Gonzalez  
J. Clayton                S. Lam  
D. Carnell               C. Edwards  
I. Amott                 R. Toffoletto  
L. Erm                   M. Glaister

##### DSTO Library

Library Fishermens Bend  
Library Maribyrnong  
Library Salisbury (2 copies)  
Australian Archives  
Library, MOD, Pyrmont (Doc Data sheet only)

### **Capability Development Division**

Director General Maritime Development (Doc Data Sheet only)  
Director General Land Development (Doc Data Sheet only)  
Director General C3I Development (Doc Data Sheet only)

### **Army**

ABCA Office, G-1-34, Russell Offices, Canberra (4 copies)  
SO (Science), DJFHQ(L), MILPO Enoggera, Queensland 4051 (Doc Data Sheet  
only)  
NAPOC QWG Engineer NBCD c/- DENGRS-A, HQ Engineer Centre Liverpool  
Military Area, NSW 2174 (Doc Data Sheet only)

### **Intelligence Program**

DGSTA Defence Intelligence Organisation

### **Corporate Support Program (libraries)**

OIC TRS, Defence Regional Library, Canberra  
Officer in Charge, Document Exchange Centre (DEC) (Doc Data Sheet)  
\*US Defence Technical Information Center, 2 copies  
\*UK Defence Research Information Centre, 2 copies  
\*Canada Defence Scientific Information Service, 1 copy  
\*NZ Defence Information Centre, 1 copy  
National Library of Australia, 1 copy

## **UNIVERSITIES AND COLLEGES**

Australian Defence Force Academy  
Library  
Head of Aerospace and Mechanical Engineering  
Senior Librarian, Hargrave Library, Monash University  
Librarian, Flinders University

## **OTHER ORGANISATIONS**

NASA (Canberra)  
AGPS

## **OUTSIDE AUSTRALIA**

### **ABSTRACTING AND INFORMATION ORGANISATIONS**

INSPEC: Acquisitions Section Institution of Electrical Engineers  
Library, Chemical Abstracts Reference Service  
Engineering Societies Library, US  
Materials Information, Cambridge Scientific Abstracts, US  
Documents Librarian, The Center for Research Libraries, US

**INFORMATION EXCHANGE AGREEMENT PARTNERS**

Acquisitions Unit, Science Reference and Information Service, UK  
Library - Exchange Desk, National Institute of Standards and Technology, US  
National Aerospace Laboratory, Japan  
National Aerospace Laboratory, Netherlands

SPARES (6 copies)

**Total number of copies:**     **64**

<b>DEFENCE SCIENCE AND TECHNOLOGY ORGANISATION DOCUMENT CONTROL DATA</b>		1. PRIVACY MARKING/CAVEAT (OF DOCUMENT)	
<b>2. TITLE</b> Performance Tests of the Original Transonic Wind Tunnel Compressor and Circuit		<b>3. SECURITY CLASSIFICATION (FOR UNCLASSIFIED REPORTS THAT ARE LIMITED RELEASE USE (L) NEXT TO DOCUMENT CLASSIFICATION)</b> Document (U) Title (U) Abstract (U)	
<b>4. AUTHOR(S)</b> Yoel Y. Link and Howard A. Quick		<b>5. CORPORATE AUTHOR</b> Aeronautical and Maritime Research Laboratory PO Box 4331 Melbourne Vic 3001 Australia	
<b>6a. DSTO NUMBER</b> DSTO-TN-0150	<b>6b. AR NUMBER</b> AR-010-527	<b>6c. TYPE OF REPORT</b> Technical Note	<b>7. DOCUMENT DATE</b> May 1998
<b>8. FILE NUMBER</b> M1/9/63	<b>9. TASK NUMBER</b> 95/181	<b>10. TASK SPONSOR</b> DSTO	<b>11. NO. OF PAGES</b> 84
<b>13. DOWNGRADING/DELIMITING INSTRUCTIONS</b> -		<b>14. RELEASE AUTHORITY</b> Chief, Air Operations Division	
<b>15. SECONDARY RELEASE STATEMENT OF THIS DOCUMENT</b> <i>Approved for public release</i>			
OVERSEAS ENQUIRIES OUTSIDE STATED LIMITATIONS SHOULD BE REFERRED THROUGH DOCUMENT EXCHANGE CENTRE, DIS NETWORK OFFICE, DEPT OF DEFENCE, CAMPBELL PARK OFFICES, CANBERRA ACT 2600			
<b>16. DELIBERATE ANNOUNCEMENT</b> No Limitations			
<b>17. CASUAL ANNOUNCEMENT</b> Yes			
<b>18. DEFTEST DESCRIPTORS</b> Pressure, Transonic wind tunnels, Compressors, Noise, Measurement			
<b>19. ABSTRACT</b> <p>A detailed test programme of the AMRL Transonic Wind Tunnel was conducted. The objective of the test programme was to determine the pressure distributions around the tunnel circuit with larger nozzle exit areas. The existing high speed contraction, test section, model support mechanism, and downstream diffuser were removed for the tests. A variable nozzle and collector were designed and installed in place of the removed components to determine the effects of increasing the nozzle exit area. Three nozzle configurations were investigated, with a 38.3%, 44.4% and 58.1% increase in area relative to the existing test section area. Measurements were made of static pressure around the tunnel circuit, total pressure upstream and downstream from the compressor, and temperatures at various locations. Noise measurements were also made outside the tunnel complex and at four locations around the boundary of the site to determine the noise level of the wind tunnel.</p>			